STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 0.000, RT.	C	VD-024	72	10		Stowe | Waterbury	5.00								2.00		12.0 ~~30~~ 12.0									INSTALL NEW VD-024 SIGN AND POSTS. LOCATE IT AT THE TOWN LINE AND OR 150' SOUTH AND ACROSS FROM POLE # GMP / 50 / 29		13	
NB	MM 0.000, RT.	C	D3-1	30	6		Stowe Hollow Rd TH 3						X		X												REMOVE EXISTING D3-1 SIGN AND POST LOCATED 150' SOUTH AND ACROSS FROM POLE # GMP / 50 / 29			
NB	MM 0.011, RT.	A	TOWN SIGN	24	30		SPEED ZONE AHEAD						X		X												REMOVE EXISTING R2-5a SIGN AND POST LOCATED 90' SOUTH AND ACROSS FROM POLE # GMP / 50 / 29			
NB	MM 0.019, RT.	A	W11-7	30	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE EXISTING W11-7 SIGN AND POST LOCATED 50' SOUTH AND ACROSS FROM POLE # GMP / 50 / 29	X		
NB	MM 0.051, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		13.0 ~~15~~									REPLACE EXISTING R2-1 SIGN AND POST LOCATED 120' NORTH AND ACROSS FROM POLE # GMP / 50 / 29	X		
NB	MM 0.516, RT.	A	W1-1MDL	36	36			9.00								2.00		13.0 ~~30~~ 13.0									INSTALL NEW W1-1Md L SIGN AND POSTS. LOCATE IT 260' SOUTH OF INTERSECTION OF UPPER HOLLOW RD		15	
		A	W13-1	18	18		30 M.P.H.	2.25																			INSTALL NEW W13-1 SIGN BELOW THE W1-1Md L SIGN LOCATED 260' SOUTH OF INTERSECTION OF UPPER HOLLOW RD ON POST CLOSEST TO ROADWAY.	X		
SB	MM 0.534, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		13.0 ~~15~~									REPLACE EXISTING R2-1 SIGN AND POST LOCATED 164' SOUTH AND ACROSS FROM THE INTERSECTION OF UPPER HOLLOW RD	X		
NB	MM 0.570, RT.	A B	D3-1	66	12		Upper Hollow Rd	5.50								2.00		12.0 ~~30~~ 12.0									INSTALL NEW D3-1 ON 2 POSTS ADJACENT R1-1 SIGN LOCATED 20' SOUTH AND ACROSS FROM POLE # 18-8 / 21		15	
		D	R1-1	30	30		STOP	6.25								1.00		14.0 ~~15~~									INSTALL NEW R1-1 SIGN AND POST. LOCATE IT 20' SOUTH AND ACROSS FROM POLE # 18-8 / 21	X		
										EA 5	EA	EA	EA	EA 5	EA		FT ~~150~~	FT	FT				LB	LB	LB	LB				
								SF 44.25	SF	EA 5				EA 5		EA 10	FT ~~150~~ 128			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
DRAWN BY: TDS
CHECKED BY: NLA
PLOT DATE: 16-JUL-2012
STOWE TRAFFIC SIGN SUMMARY SHEET 1
SHEET 51 **OF** 107