STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 2

STOWE
STOWE HOLLOW RD

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) lb/ft 1.75 / 1.88 | SQUARE STEEL (in) lb/ft 2.00 / 2.42 | SQUARE STEEL (in) lb/ft 2.50 / 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) lb/ft 3.00 / 7.60 | TUBULAR STEEL O/(in) lb/ft 3.50 / 9.00 | TUBULAR STEEL O/(in) lb/ft 4.00 / 10.80 | TUBULAR STEEL O/(in) lb/ft 5.00 / 14.60 | SIGN FRAME REQUIRED | REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK) | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NB | MM 0.587, RT. | A | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | X | | X | 1.00 | | 13.0 ~~15~~ | | | | | | | | REPLACE EXISTING R2-1 SIGN AND POST LOCATED 85' NORTH AND ACROSS FROM POLE # 18-8 / 21 | X | | |
| SB | MM 0.604, LT. | F | W1-MDR | 36 | 36 | | | 9.00 | | | | | | | | 2.00 | | 14.0 ~~30~~ 14.0 | | | | | | | | INSTALL NEW W1-1Md R SIGN AND POSTS. LOCATE IT 70' SOUTH AND ACROSS FROM POLE # 52 / 37 | | 15 | |
| | | F | W13-1 | 18 | 18 | | 30 M.P.H. | 2.25 | | | | | | | | | | | | | | | | | | INSTALL NEW W13-1 SIGN BELOW THE W1-1Md R SIGN LOCATED 70' SOUTH AND ACROSS FROM POLE # 52 / 37 | X | | |
| NB | MM 0.739, RT. | A | W1-1L | 30 | 30 | | | 6.25 | | | | | | | | 1.00 | | 15 | | | | | | | | INSTALL NEW W1-1 L SIGN AND POST. LOCATE IT 53' NORTH OF POLE # 52 / 35 | X | | |
| | | A | W13-1 | 18 | 18 | | 30 M.P.H. | 2.25 | | | | | | | | | | | | | | | | | | INSTALL NEW W13-1 SIGN BELOW THE W1-1 L SIGN LOCATED 53' NORTH OF POLE # 52 / 35 | X | | |
| NB | MM 0.761, RT.<br>MM 0.761, RT.<br>MM 0.799, RT. | A<br>B | | 6 | 8 | | (8) TYPE II - 6" x 8" WHITE DELINEATORS | | | | | | | | | | | 72.0 | | | | | | | | INSTALL NEW DELINEATORS (8) BACK-TO-BACK 55" APART ON 4 POST. INSTALL FIRST POST 95' SOUTH OF POLE # 34 / NET / 17 ON POST CLOSEST TO ROADWAY. | | 5 | |
| SB | MM 0.803, LT. | F | W1-1R | 30 | 30 | | | 6.25 | | | | | | | | 1.00 | | 16.0 ~~15~~ | | | | | | | | INSTALL NEW W1-1 R SIGN AND POST. LOCATE IT 90' SOUTH AND ACROSS FROM POLE # 33 / NET / 818 / 16 | X | | |
| | | F | W13-1 | 18 | 18 | | 30 M.P.H. | 2.25 | | | | | | | | | | | | | | | | | | INSTALL NEW W13-1 SIGN BELOW THE W1-1 R SIGN LOCATED 90' SOUTH AND ACROSS FROM POLE # 33 / NET / 818 / 16 | X | | |
| NB | MM 0.853, RT.<br>MM 0.886, RT. | A<br>B | | 6 | 8 | | (6) TYPE II - 6" x 8" WHITE DELINEATORS | | | | | | | | | | | 27.0 | | | | | | | | INSTALL NEW DELINEATORS (6) BACK-TO-BACK 60" APART ON 3 POST. INSTALL FIRST POST 175' NORTH OF POLE # 33 / NET / 818 / 16 ON POST CLOSEST TO ROADWAY. | | 5 | |
| SB | MM 0.964, LT. | F | W11-7 | 30 | 30 | | | 6.25 | | | | | X | | X | 1.00 | | 14.0 15 | | | | | | | | REPLACE EXISTING W11-7 SIGN AND POST LOCATED 760' NORTH AND ACROSS FROM POLE # 33 / NET / 818 / 16 | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | EA | EA | EA | EA 2 | EA | EA 2 | | FT | FT ~~90~~ | FT | | | | | LB | | | | | |
| | | | | | | | 14 DELINEATORS | SF 39.50 | SF | EA 2 | | | | EA 2 | | EA 6 | FT ~~90~~ 185 | | | EA | LB | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
STOWE TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 52 OF 107