STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.038, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		12.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 245' SOUTH AND ACROSS FROM POLE # 3 / 18 / 11 / NET	X		
NB	MM 1.110, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 140' NORTH OF POLE # 3 / 18 / 11 / NET	X		
SB	MM 1.523, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		12.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 220' SOUTH AND ACROSS FROM UPPER HOLLOW RD INTERSECTION	X		
NB	MM 1.540, RT.	A	W1-1MDL	36	36			9.00								2.00		14.0 ~~30~~ 15.0								INSTALL NEW W1-1Md L SIGN AND POSTS. LOCATE IT 135' SOUTH OF INTERSECTION OF UPPER HOLLOW RD		15	
		A	W13-1	18	18		30 M.P.H.	2.25																		INSTALL NEW W13-1 SIGN BELOW THE W1-1Md L SIGN LOCATED 135' SOUTH OF INTERSECTION OF UPPER HOLLOW RD	X		
NB	MM 1.566, RT.	A B	D3-1	66	12		Upper Hollow Rd	5.50					X			2.00		11.5 ~~30~~ 11.5								INSTALL NEW D3-1 ON 2 POSTS ADJACENT R1-1 SIGN LOCATED AT THE INTERSECTION OF STOWE HOLLOW ROAD AND UPPER HOLLOW ROAD		15	
		D	R1-1	30	30		STOP	6.25								1.00		13.0 ~~15~~								INSTALL NEW R1-1 SIGN AND POST. AT THE NORTHEAST CORNER OF THE INTERSECTION OF STOWE HOLLOW ROAD AND UPPER HOLLOW RD	X		
SB	MM 1.605, LT.	F	W1-1MDL	36	36			9.00								2.00		16.0 ~~30~~ 16.0								INSTALL NEW W1-1Md R SIGN AND POSTS. LOCATE IT ADJACENT TO POLE # 7		15	
		F	W13-1	18	18		30 M.P.H.	2.25																		INSTALL NEW W13-1 SIGN BELOW THE W1-1Md R SIGN LOCATED ADJACENT TO POLE # 7	X		
NB	MM 1.605, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED ACROSS FROM POLE # 7	X		
NB	MM 1.761, RT.	A		6	8		(1) TYPE II - 6" x 8" WHITE DELINEATOR											8.0								INSTALL 1 DELINEATOR IN FRONT OF LARGE TREE LOCATED 824' NORTH AND ACROSS FROM POLE # 7		5	
NB	MM 1.770, RT.	A		6	8		(1) TYPE II - 6" x 8" WHITE DELINEATOR											8.0								INSTALL 1 DELINEATOR IN FRONT OF LARGE TREE LOCATED 702' SOUTH OF POLE # 5 /2		5	
										EA	EA	EA	EA 4	EA	EA 4		FT	FT 165	FT		LB	LB	LB	LB					
							2 DELINEATORS	SF 54.25	SF	EA ~~4~~ 5				EA 4		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
STOWE TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 53 **OF** 107