STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 2.386, RT.	A	W3-1	30	30			6.25								1.00		15								INSTALL NEW W3-1 SIGN AND POST. LOCATE IT 200' NORTH OF POLE # VofS / 14 / 18 / 70	X		
SB	MM 2.414, RT.	F	R1-2	36	36			3.89								1.00		13.0 ~~15~~								INSTALL NEW R1-2 SIGN AND POST. LOCATE IT 350' NORTH AND ACROSS FROM POLE # V of S / 14 / 18 / 70 FOR WEST LEG OF Y-INTERSECTION	X		
SB	MM 2.415, LT.	EF	D3-1	66	12			5.50					X		X	2.00		12.0 ~~30~~ 12.0								REPLACE EXISTING D3-1 SIGN AND INSTALL ON LOCATED IN THE ISLAND 2 POSTS ADJACENT TO THE INTERSECTION OF GOLD BROOK RD		15	
SB	MM 2.416, LT.	E	R1-1	30	30			6.25								1.00		13.0 ~~15~~								INSTALL NEW R1-1 SIGN AND POST. LOCATE IT ON THE WESTERN END OF ISLAND AT INTERSECTION WITH GOLD BROOK RD ON RIGHT SIDE OF WESTERLY LEG OF Y-INTERSECTION	X		
NB	MM 2.416, RT.	J	D3-1	48	12			4.00								~~2.00~~		~~30~~								INSTALL NEW D3-1 SIGN ON 2-POSTS DIRECTLY ACROSS GOLDBROOK ROAD FROM THE CENTER OF THE WESTERLY LEG OF THE WYE INTERSECTION OF STOWE HOLLOW RD		15	
NB	MM 2.423, RT.	A	R1-1	30	30			6.25								1.00		13.0 ~~15~~								INSTALL NEW R1-1 SIGN AND POST. LOCATE IT 325' SOUTH AND ACROSS FROM POLE # 51 / 1	X		
SB	MM 2.423, LT.	EF	D3-1	30	8								X													REMOVE EXISTING D3-1 SIGN LOCATED 325'SOUTH OF POLE # 51 / 1			
		HG	D3-1	72	12			6.00					X		X	2.00		18.0 18.0 ~~30~~								REPLACE EXISTING D3-1 SIGN AND INSTALL ON 2 POSTS LOCATED 325' SOUTH OF POLE # 51 / 1		15	
NB	MM 2.540, RT.	A	TOWN SIGN	30	30								X		X											REMOVE EXISTING TOWN SIGN LOCATED 290' NORTH AND ACROSS FROM POLE # 51 / 1			
NB	MM 2.582, RT.	A	W11-1	30	30			6.25					X		X	1.00		16.0 ~~15~~								REPLACE EXISTING SIGN AND POST LOCATED 10' SOUTH OF POLE # 5 / 21 / 3½	X		
		A	W16-1	18	24			3.00																		INSTALL NEW SIGN BELOW THE W11-1 SIGN LOCATED 10' SOUTH OF POLE # 5 / 21 / 3½	X		
		A	TOWN SIGN	30	30								X		X											REMOVE EXISTING SIGN AND POST.			
										EA	EA	EA	EA 6	EA	EA 5		FT	FT ~~135~~	FT		LB	LB	LB	LB					
								SF 47.39	SF	EA 6				EA 5		EA 9	FT ~~135~~ 160			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
STOWE TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 55 OF 107