STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 2.582, LT.	F	W11-1	30	30			6.25					X		X	1.00		16.0 ~~15~~								REPLACE EXISTING SIGN AND POST LOCATED 10' SOUTH AND ACROSS FROM POLE # 5 / 21 / 3½	X		
		F	W16-1	18	24			3.00																		INSTALL NEW SIGN BELOW THE W11-1 SIGN LOCATED 10' SOUTH AND ACROSS FROM POLE # 5 / 21 / 3½	X		
		F	TOWN SIGN	30	30								X		X												REMOVE EXISTING SIGN AND POST.			
SB	MM 2.692, LT.	F	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 570' NORTH AND ACROSS FROM POLE # 5 / 21 / 3½	X		
NB	MM 2.958, RT.	A	W3-1	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST. LOCATE IT 90' NORTH AND ACROSS FROM POLE # V of S / 5 / 30 / 55	X		
SB	MM 3.015, LT.	F	R2-1	24	30			5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 105' SOUTH AND ACROSS FROM POLE # 5 / 32 / 1812	X		
NB	MM 3.030, RT.	D	R1-2	36	36			3.89					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R1-2 SIGN AND POST. LOCATE IT AT THE SOUTH END OF ISLAND, 25' SOUTH OF POLE # 5 / 32 / 1812	X		
NB	MM 3.035, RT.	CD	D3-1	66	12			5.50					X		X	2.00		12.0 ~~30~~ 12.0								REPLACE EXISTING D3-1 SIGN ON POSTS LOCATED IN THE ISLAND ADJACENT TO POLE # 5 / 32 / 1812		15	
NB	MM 3.037, RT.	A	R1-1	30	30			6.25					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R1-1 SIGN AND POST. LOCATE IT ADJACENT TO POLE # 5 / 32 / 1812	X		
										EA	EA	EA	EA 7	EA	EA 7		FT	FT ~~120~~	FT									
								SF 41.14	SF	EA 7				EA 7		EA 8	FT ~~120~~ 108			EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
STOWE TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 56 **OF** 107