STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 3.170, RT.	A	W11-2	30	30								X		X											REMOVE EXISTING SIGN AND POST LOCATED 400' NORTH AND ACROSS FROM POLE # NET / 51 / 5 / 34			
SB	MM 3.319, LT.	F	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 50' SOUTH OF POLE # 18 / 44 / 41	X		
NB	MM 3.390, RT.	D	R1-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R1-1 SIGN AND POST. LOCATE 325' NORTH AND ACROSS FROM POLE # 18 / 44 / 41	X		
		AB	D3-1	42	12			3.50					I													REPLACE EXISTING D3-1 SIGN AND INSTALL ON ABOVE OF R1-1 SIGN LOCATED 325' NORTH AND ACROSS FROM POLE # 18 / 44 /41ON SAME POST		15	
SB	MM 3.390, RT.	F	W11-2	30	30								X		X											REMOVE EXISTING SIGN AND POST LOCATED 325' NORTH OF POLE # 18 / 44 / 41			
NB	MM 3.440, RT.	A	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 260' NORTH OF THE INTERSECTION WITH GILCRIST RD	X		
NB	MM 3.640, RT.	A	W1-2R	30	30			6.25					X		X	1.00		16.0 ~~15~~								REPLACE EXISTING W1-2 R SIGN AND POST LOCATED 60' NORTH AND ACROSS FROM POLE # 1 / 0 / 9 / 4	X		
NB	MM 3.667, RT.	A	S3-1	36	36	FYG		9.00					X		X	2.00		14.0 ~~30~~ 14.0								REPLACE EXISTING S3-1 SIGN AND INSTALL ON 2 POSTS LOCATED 195' NORTH AND ACROSS FROM POLE # 1 / 0 / 9 / 4	X		
SB	MM 3.669, LT. TO MM 3.749, LT.	EF		6	8		(14) TYPE II - 6" x 8" WHITE DELINEATORS											63								INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60' APART ON 7 POSTS, INSTALL FIRST POST ADJACENT TO POLE # 34 / 5 / 50		5	
SB	MM 3.684, LT.	F	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 80' NORTH OF POLE # 34 / 5 / 50	X		
										EA	EA	EA	EA ~~8~~	EA	EA 8		FT	FT ~~105~~	FT		LB	LB	LB	LB					
							14 DELINEATORS	SF 40.00	SF	EA ~~8~~ 9				EA 8		EA 7	FT ~~105~~ 163			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
STOWE TRAFFIC SIGN SUMMARY SHEET 8

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 58 OF 107