

TRAFFIC SIGN SUMMARY SHEET 10

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL								
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RE-PAI-N		RE-MOV-E	FOUNDATION			FOUNDATION					DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER						
																	1.75	2.00	2.50	3.00	3.50	4.00						5.00					
SB	MM 4.030, LT.	F	R2-1	24	30			5.00						X	X	1.00	14.0	15							REPLACE EXISTING R2-1 SIGN AND POST LOCATED 400' NORTH OF POLE # 5 / 60 / 19	X							
NB	MM 4.454, RT.	A	W1-2L	30	30			6.25						X	X	1.00	14.0	15							REPLACE EXISTING W1-2 L SIGN AND POST LOCATED ACROSS FROM POLE # 5 / 75 / 4	X							
NB	MM 4.482, RT.	A	W3-1	30	30			6.25						X	X	1.00	15								REPLACE EXISTING W3-1 SIGN AND POST LOCATED 150' SOUTH AND ACROSS FROM POLE # 3 / 76	X							
SB	MM 4.488, LT.	F	R2-1	24	30			5.00						X	X	1.00	13.0	15							REPLACE EXISTING R2-1 SIGN AND POST LOCATED 20' NORTH OF POLE # 3 / 76	X							
SB	MM 4.510, LT.	E	R5-1	30	30			6.25								1.00	15								INSTALL NEW R5-1 SIGN AND POST. LOCATE 137' NORTH OF POLE # 3 / 76	X							
		H	R6-1R	36	12			3.00																	INSTALL NEW R6-1R BELOW THE R1-1. SIGN ON LEFT SIDE OF THE POST TO INDICATE FLOW OF TRAFFIC APPROACHING THE YIELD CONDITION FROM SCHOOL ST/ TABOR HILL RD	X							
		G	R6-1L	36	12			3.00																	INSTALL NEW R6-1R BELOW THE R1-1. SIGN ON RIGHT SIDE OF THE POST TO INDICATE FLOW OF TRAFFIC APPROACHING THE YIELD CONDITION FROM SCHOOL ST/ TABOR HILL RD	X							
SB	MM 4.510, LT.	F	R1-2	36	36			3.89								1.00	13.0	15							INSTALL NEW R1-2 SIGN AND POST. LOCATE 140' NORTH OF POLE # 3 / 76	X							
SB	MM 4.520, LT.	E	OM1-1	18	18			2.25								1.00	10.0	8							INSTALL NEW OM1-1 SIGN AND POST. LOCATE 157' NORTH OF POLE # 3 / 76 AND OR ON THE SOUTH WEST SIDE OF ISLAND	X							
SB	MM 4.520, LT.	E	R5-1	30	30			6.25						X	X	1.00	15								REPLACE EXISTING R5-1 SIGN AND POST. LOCATE 157' NORTH OF POLE # 3 / 76 AND OR ON THE SOUTH WEST SIDE OF ISLAND	X							
		H	R6-1R	36	12			3.00																	INSTALL NEW R6-1R BELOW THE R1-1. SIGN ON LEFT SIDE OF THE POST TO INDICATE FLOW OF TRAFFIC APPROACHING THE YIELD CONDITION FROM SCHOOL ST/ TABOR HILL RD	X							
		G	R6-1L	36	12			3.00																	INSTALL NEW R6-1R BELOW THE R1-1. SIGN ON RIGHT SIDE OF THE POST TO INDICATE FLOW OF TRAFFIC APPROACHING THE YIELD CONDITION FROM SCHOOL ST/ TABOR HILL RD	X							
NB	MM 4.549, RT.	A	R1-1	30	30			6.25						X	X	1.00	13.0	15							REPLACE EXISTING R1-1 SIGN AND POST LOCATED ON THE NORTH EAST CORNER OF INTERSECTION.	X							
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".																																	
								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA