STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

STOWE
STOWE HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							UPPER HOLLOW RD																						
EB	MM 0.030, RT. SOUTH END	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		17.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST. LOCATE 150' EAST OF INTERSECTION OF SCHOOL ST/TABOR HILL ROAD WITH STOW HOLLOW ROAD	X		
EB	MM 0.010, RT. NORTH END	AB	D3-1	66	12		Upper Hollow Rd	5.50					~~X~~		X	2.00		13.0 ~~30~~ 13.0								REPLACE EXISTING D3-1 SIGN AND INSTALL ON 2 POSTS. LOCATED 25' EAST OF POLE # 5 / 32 / 1812		15	
EB	MM 0.030, RT. NORTH END	A	R1-1	30	30		STOP	6.25					~~X~~		X	1.00		14.0 ~~15~~								REPLACE EXISTING R1-1 SIGN AND POST LOCATE 70' EAST OF POLE # 5 / 32 / 1812	X		
							COVERED BRIDGE RD																						
WB	MM 0.020, LT.	F	R2-1	24	30		SPEED LIMIT 25	5.00					2 ~~X~~		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATE 70' WEST OF INTERSECTION	X		
							GILCRIST RD																						
EB	MM 0.020, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATE 75' EAST OF INTERSECTION	X		
										EA	EA	EA	EA ~~5~~	EA	EA 5		FT	FT ~~90~~	FT		LB	LB	LB	LB					
								SF 26.75	SF	EA ~~5~~ 4				EA 5		EA 6	FT ~~90~~ 80			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 19-JUL-2012
DRAWN BY: TDS
CHECKED BY: JLS