STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.00 (2.42)	SQUARE STEEL (in) lb/ft 2.50 (3.35)	TUBULAR STEEL O/(in) lb/ft FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00 (7.60)	TUBULAR STEEL O/(in) lb/ft 3.50 (9.00)	TUBULAR STEEL O/(in) lb/ft 4.00 (10.80)	TUBULAR STEEL O/(in) lb/ft 5.00 (14.60)	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 2.542, RT. + 300 FT, RT.	D	W3-1	30	30			6.25								1.00		~~15~~								INSTALL A NEW W3-1 SIGN AND POST. LOCATE IT 25' NORTH OF POLE # 63 ON LEDUC RD	X		
WB	MM 2.630, LT.	F	W2-1	36	36			9.00								2.00		16.0 ~~30~~ 16.0								INSTALL A NEW W2-1 SIGN AND POST 460' EAST OF PEA RIDGE RD	X		
		F	W16-8P	48	15			5.00																		INSTALL A NEW W16-8aP SIGN BELOW THE W2-1 SIGN LOCATED 460' EAST OF PEA RIDGE RD		16	
EB	MM 3.040, RT.	A	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING W3-1 SIGN AND POST. LOCATE IT 360' WEST OF POLE # 68 / 5	X		
EB	MM 3.077, RT.	F	W2-1	30	30			6.25								1.00		15								INSTALL A NEW W2-1 SIGN AND POST 365' WEST OF POLE # 68 / 5	X		
		F	W16-8P	30	8			1.67																		INSTALL A NEW W16-8P SIGN BELOW THE W2-1 SIGN LOCATED 365' WEST OF POLE # 68 / 5		16	
WB	MM 3.090, LT.	G	VD-024	72	10			5.00					1			2.00		13.0 ~~30~~ 13.0								INSTALL A NEW VD-024 SIGN ON 2 POSTS. LOCATE IT 95' WEST AND ACROSS FROM POLE # 68 / 5		16	
EB	MM 3.120, RT.	A	R1-1	30	30			6.25				1	X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED 63' EAST OF POLE # 68 / 5	X		
		A	R1-3P	18	6			0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 SIGN LOCATED 63' EAST OF POLE # 68 / 5	X		
EB	MM 3.120, RT. + 50 FT,	C	R2-1	24	30			5.00					1	X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 63' EAST AND 50' SOUTH OF POLE # 68 / 5	X		
WB	MM 3.120, LT.	H	R1-1	30	30			6.25					X		X	1.00		15								REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED 63' EAST AND ACROSS FROM POLE # 68 / 5	X		
												EA 2 ~~4~~	EA ~~4~~	EA 4	EA			FT ~~150~~	FT			LB	LB	LB	LB					
								SF 57.67	SF			EA 2 ~~4~~ 5		EA 4	EA 10			FT ~~150~~ 146		EA		LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL 4
SHEET 66 OF 107