STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		H	R1-3P	18	6		ALL WAY	0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 SIGN LOCATED 63' EAST AND ACROSS FROM POLE # 68 / 5	X		
EB	MM 3.125, RT.	D	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED 53' WEST OF POLE # 68	X		
		D	R1-3P	18	6		ALL WAY	0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 SIGN LOCATED 53' WEST OF POLE # 68	X		
WB	MM 3.125, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED 53' WEST AND ACROSS FROM POLE # 68	X		
		F	R1-3P	18	6		ALL WAY	0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 SIGN LOCATED 53' WEST AND ACROSS FROM POLE # 68	X		
WB	MM 3.125, LT. + 50 FT	G	R2-1	24	30		SPEED LIMIT 35	5.00				I	X		X	1.00		13.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 53' WEST AND ACROSS AND 50' NORTH OF POLE # 68	X		
EB	MM 3.149, RT.	A	R2-1	24	30		SPEED LIMIT 40	5.00				I	X		X	1.00		16.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 75' EAST OF POLE # 68	X		
WB	MM 3.180, LT.	F	W2-1	30	30			6.25								1.00		15								INSTALL A NEW W2-1 SIGN AND POST. LOCATE IT ACROSS FROM POLE # 426 / 13 / 10T	X		
		F	W16-8P	30	8		Lime Kiln Rd	1.67																		INSTALL A NEW W16-8P BELOW THE W2-1 SIGN. LOCATE IT ACROSS FROM POLE # 426 / 13 / 10T		16	
WB	MM 3.220, LT.	F	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING W3-1 SIGN AND POST LOCATED 50' WEST AND ACROSS FROM POLE # 12	X		
EB	MM 3.347, RT.	F	W5-2	36	36		NARROW BRIDGE	9.00								2.00		16.0 ~~30~~ 16.0								INSTALL NEW W5-2 SIGN AND POST LOCATE 176 FT EAST OF POLE # 9 AND 250 FT WEST OF THE BRIDGE	X		
WB	MM 3.394, LT.	E	OM3-R	12	36			3.00					X		X	1.00		11.0 ~~15~~								REPLACE THE EXISTING OM3-R SIGN AND POST LOCATED 74' EAST OF POLE 9	X		
										EA	EA	EA 2	EA 6	EA	EA 6		FT	FT ~~135~~	FT		LB	LB	LB	LB				
								SF 50.92	SF	EA 2	6			EA 6		EA 9	FT	~~135~~ 129		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA