STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL IN SHSM	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 3.394, RT.	A	OM3-L	12	36			3.00					X		X	1.00		12.0 ~~15~~									REPLACE THE EXISTING OM3-L SIGN AND POST. LOCATE IT 74' EAST AND ACROSS FROM POLE 9	X		
WB	MM 3.408, RT.	F	OM3-L	12	36			3.00					X		X	1.00		11.0 ~~15~~									REPLACE THE EXISTING OM3-L SIGN AND POST LOCATED 148' EAST OF POLE 9	X		
WB	MM 3.408, LT.	B	OM3-R	12	36			3.00					X		X	1.00		12.0 ~~15~~									REPLACE THE EXISTING OM3-R SIGN AND POST. LOCATE IT 148' EAST AND ACROSS FROM POLE 9	X		
WB	MM 3.220, LT.	F	W5-2	36	36			9.00								2.00		14.0 ~~30~~ 14.0									INSTALL NEW W5-2 SIGN AND POST LOCATE 70 FT EAST OF AND ACROSS FROM POLE # 8 AND 1964 FT WEST AND ACROSS FROM STOP AHEAD SIGN ASSEMBLY AT MM 3.827	X		
EB	MM 3.827, RT.	A	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING W3-1 SIGN AND POST LOCATED 470' WEST OF NORTH ST.	X		
EB	MM 3.860, RT.	A	W2-1	30	30			6.25								1.00		15									INSTALL A NEW W2-1 SIGN AND POST LOCATED 295' WEST OF NORTH ST.	X		
		A	W16-8P	24	8			1.34																			INSTALL A NEW W16-8P SIGN BELOW THE W2-1 SIGN LOCATED 295' WEST OF NORTH ST.		16	
WB	MM 3.895, LT.	F	R2-1	24	30			5.00			I		X		X	1.00		13.0 ~~15~~									REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 110' WEST OF NORTH ST.	X		
EB	MM 3.913, RT.	A	R1-1	24	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF NORTH ST	X		
		A	R1-3P	18	6			0.75																			INSTALL A NEW R1-3P SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF NORTH ST	X		
WB	MM 3.913, LT.	H	R1-1	30	30			6.25			I		X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED ON THE NORTHWEST CORNER OF NORTH ST	X		
								SF 50.09	SF	EA 7			EA 7		EA 7	EA 10		FT ~~150~~ 133		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL 6 **SHEET** 68 **OF** 107