STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.00 (2.42)	SQUARE STEEL (in) lb/ft 2.50 (3.35)	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00 (7.60)	TUBULAR STEEL O/(in) lb/ft 3.50 (9.00)	TUBULAR STEEL O/(in) lb/ft 4.00 (10.80)	TUBULAR STEEL O/(in) lb/ft 5.00 (14.60)	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL IN SHSM	SIGN DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
		H	R1-3P	18	6		ALL WAY	0.75																			INSTALL A NEW R1-3P SIGN AND POST LOCATED ON THE NORTHWEST CORNER OF NORTH ST	X		
EB	MM 3.913, RT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED ON THE NORTHEAST CORNER OF NORTH ST	X		
		A	R1-3P	18	6		ALL WAY	0.75																			INSTALL A NEW R1-3P SIGN AND POST LOCATED ON THE NORTHEAST CORNER OF NORTH ST	X		
EB	MM 3.920, RT. + 350 FT	D	W3-1	30	30			6.25					~~X~~		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING W3-1 SIGN AND POST. LOCATE ON NORTH ST, 50' NORTH OF MAIL BOX 2157	X		
WB	MM 3.920, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED ON THE SOUTHEAST CORNER OF NORTH ST	X		
		F	R1-3P	18	6		ALL WAY	0.75																			INSTALL A NEW R1-3P SIGN AND POST LOCATED ON THE SOUTHEAST CORNER OF NORTH ST	X		
EB	MM 3.943, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00				I	X		X	1.00		15									REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 140' EAST OF NORTH ST	X		
WB	MM 3.975, LT.	F	W2-1	30	30			6.25					I			1.00		15									INSTALL A NEW W2-1 SIGN AND POST LOCATED 312' EAST OF NORTH ST	X		
		F	W16-8P	24	8		North St	1.34																			INSTALL A NEW W16-8P SIGN BELOW THE W2-1 SIGN LOCATED 312' EAST OF NORTH ST		16	
WB	MM 4.020, LT.	F	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING W3-1 SIGN AND POST LOCATED 530' EAST OF NORTH ST	X		
EB	MM 4.350, RT.	A	W1-2L	30	30			6.25								1.00		14.0 ~~15~~									INSTALL A NEW W1-2 SIGN AND POST. LOCATE IT 2270' EAST OF NORTH ST	X		
										EA	EA	EA I	EA 5	EA	EA 5		FT	FT ~~105~~	FT		LB	LB	LB	LB					
								SF 46.09	SF	EA I 5				EA 5		EA 7	FT ~~105~~ 100			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn PLOT DATE: 16-JUL-2012
PROJECT LEADER: JLS DRAWN BY: TDS
DESIGNED BY: NLA CHECKED BY: NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL 7 SHEET 69 OF 107