STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft	SQUARE STEEL (in) 2.00 lb/ft	SQUARE STEEL (in) 2.50 lb/ft	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft	TUBULAR STEEL O/(in) 3.50 lb/ft	TUBULAR STEEL O/(in) 4.00 lb/ft	TUBULAR STEEL O/(in) 5.00 lb/ft	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL IN SHSM	SIGN DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
EB	MM 5.170, RT. TO MM 5.230, RT.	A B		6	8		(10) TYPE II - 6" x 8" WHITE DELINEATORS									5		45								INSTALL NEW DELINEATORS (10) BACK - TO - BACK 60' APART ON 5 POSTS, INSTALL FIRST POST 554' WEST AND ACROSS FROM POLE # 20		5	
EB	MM 5.190, RT.	A	W1-8L	18	24								X		X												REMOVE EXISTING CHEVRON AND POST LOCATED 450' WEST AND ACROSS FROM POLE # 20			
EB	MM 5.205, RT.	A	R2-1	24	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 370' WEST AND ACROSS FROM POLE # 20	X		
EB	MM 5.250, RT.	A	W1-1R	30	30								X		X												REMOVE EXISTING R1-1 SIGN AND POST LOCATED 130" WEST AND ACROSS FROM POLE # 20			
WB	MM 5.260, LT.	F	W1-2R	30	30			6.25								1.00		13.0 ~~15~~								INSTALL A NEW R2-1 SIGN AND POST LOCATED 80' WEST OF POLE # 20	X		
WB	MM 5.785, LT.	F	VR-017	24	30								X		X												REMOVE EXISTING VR-017 SIGN AND POST LOCATED 110' EAST AND ACROSS FROM POLE # 11			
WB	MM 5.785, LT.	F	R2-1	24	30			5.00					X			1.00		13.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 110' EAST AND ACROSS FROM POLE # 11	X		
EB	MM 5.788, RT.	A	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 127' EAST OF POLE # 11	X		
WB	MM 5.870, LT.	F	W8-3	36	36			9.00								1.00 2.00		15.0 ~~30~~								INSTALL A NEW W8-3 SIGN AND POSTS. LOCATE IT 106' EAST AND ACROSS FROM POLE # 9	X		
										EA	EA	EA	EA 6	EA	EA 5		FT	FT ~~90~~	FT		LB	LB	LB	LB					
							10 DELINEATORS	SF 31.50	SF	EA 6				EA 5		EA 6	FT ~~90~~ 114			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL 10
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 72 OF 107