STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.00 (2.42)	SQUARE STEEL (in) lb/ft 2.50 (3.35)	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00 (7.60)	TUBULAR STEEL O/(in) lb/ft 3.50 (9.00)	TUBULAR STEEL O/(in) lb/ft 4.00 (10.80)	TUBULAR STEEL O/(in) lb/ft 5.00 (14.60)	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM 6.280, RT.	A	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING W3-1 SIGN AND POST LOCATED 211' WEST AND ACROSS FROM POLE # 65/1	X		
EB	MM 6.327, RT.	A	W2-1	30	30			6.25								1.00		15								INSTALL A NEW W2-1 SIGN AND POST. LOCATE IT 40' EAST AND ACROSS FROM POLE 3 65 / 1	X		
		A	W16-8P	24	8			1.34																		INSTALL NEW W16-8P BELOW THE W2-1 LOCATED 40' EAST AND ACROSS FROM POLE 3 65 / 1		16	
WB	MM 6.376, LT.	F	R2-1	24	30			5.00				I	X		X	1.00		13.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 296' EAST OF POLE # 65 / 1	X		
EB	MM 6.377, RT.	A	R1-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 300' EAST AND ACROSS FROM POLE # 65 / 1	X		
		A	R1-3P	18	6			0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 LOCATED 300' EAST AND ACROSS FROM POLE # 65 / 1	X		
EB	MM 6.377, RT. + 50 FT	C	R2-1	24	30			5.00				I	X		X	1.00		13.0 ~~15~~								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 300' EAST AND 50' SOUTH OF POLE # 65 / 1	X		
WB	MM 6.377, LT.	H	R1-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 300' EAST OF POLE # 65 / 1	X		
		H	R1-3P	18	6			0.75																		INSTALL A NEW R1-3P SIGN BELOW THE R1-1 LOCATED 300' EAST OF POLE # 65 / 1	X		
WB	MM 6.377, LT. + 250 FT	H	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING W3-1 SIGN AND POST LOCATED 300' EAST AND 350' NORTH OF POLE # 65 / 1	X		
								EA	EA	EA 2	EA 6	EA	EA 6				FT	FT ~~105~~	FT										
								SF 44.09	SF	EA 2 6			EA 6			EA 7	FT ~~105~~ 97			EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL II

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 73 OF 107