STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

WALTHAM - FERRISBURGH - NEW HAVEN - BRISTOL
PLANK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 6.380, RT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 264' WEST AND ACROSS FROM POLE # 648 / 13	X		
		A	R1-3P	18	6		ALL WAY	0.75																			INSTALL A NEW R1-3P SIGN BELOW THE R1-1 LOCATED 264' WEST AND ACROSS FROM POLE # 648 / 13	X		
EB	MM 6.380, RT.	D	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING W3-1 SIGN AND POST. LOCATE IT 264' EAST AND ACROSS AND 350' SOUTH FROM POLE # 648 / 13	X		
WB	MM 6.380, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		15									REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 264' WEST OF POLE # 648 / 13	X		
		F	R1-3P	18	6		ALL WAY	0.75																			INSTALL A NEW R1-3P SIGN BELOW THE R1-1 LOCATED 264' WEST OF POLE # 648 / 13	X		
EB	MM 6.420, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE 50' WEST AND ACROSS FROM POLE # 648 / 13	X		
WB	MM 6.481, LT.	F	W3-1	30	30			6.25					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING W3-1 SIGN AND POST. LOCATE IT 116' WEST OF POLE # 2	X		
EB	MM 6.738, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		14.0 ~~15~~									REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE 10' WEST AND ACROSS FROM POLE # 64 / 6	X		
		A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X														REMOVE THE EXISTING VR-017 SIGN UNDER THE R2-1 SIGN LOCATED 10' WEST OF POLE # 64 / 6			
WB	MM 6.738, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		13.0 ~~15~~									REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE 10' WEST AND ACROSS FROM POLE # 64 / 6	X		
										EA	EA	EA	EA 8	EA	EA 7		FT	FT ~~105~~	FT		LB	LB	LB	LB					
								SF 41.50	SF	EA 8				EA 7		EA 7	FT ~~105~~ 98			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k018wrk.dgn PLOT DATE: 16-JUL-2012
PROJECT LEADER: JLS DRAWN BY: TDS
DESIGNED BY: NLA CHECKED BY: NLA
WALTHAM-FERRISBURGH-NEW HAVEN-BRISTOL 12 SHEET 74 OF 107