

# TRAFFIC SIGN SUMMARY SHEET 13

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL									
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	P-1		P-2	P-3	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER				
																															lb/ft	lb/ft	lb/ft	lb/ft
EB	MM 6.739, RT.	C	VD-024	72	10			5.00					X	X	2.00		11.0								REPLACE THE EXISTING VD-024 SIGN AND POSTS. LOCATE IT 5' WEST OF POLE # 64 / 6		14							
EB	MM 7.210, RT.	A	W3-1	30	30			6.25							1.00		12.0								INSTALL A NEW W3-1 SIGN AND POST. LOCATE IT 150' WEST OF POLE # 15	X								
WB	MM 7.245, LT.	F	R2-1	24	30			5.00					X	X	1.00		13.0								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 60' EAST AND ACROSS FROM POLE # 15	X								
		F	VR-017	24	30								X												REMOVE THE EXISTING VR-017 SIGN BELOW THE R2-1 SIGN LOCATED 60' EAST AND ACROSS FROM POLE # 15									
EB	MM 7.314, RT.	A	R1-1	30	30			6.25					X	X	1.00		14.0								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 160' EAST OF POLE # 64 / 16	X								
WB	MM 7.314, LT.	E	R1-1	30	30			6.25							1.00		14.0								INSTALL A NEW R1-1 SIGN AND POST. LOCATE IT 160' EAST AND ACROSS FROM POLE # 64 / 16	X								
EB	MM 7.320, RT.	B	R1-1	30	30			6.25							1.00		14.0								INSTALL A NEW R1-1 SIGN AND POST. LOCATE IT 190' EAST OF POLE # 64 / 16	X								
WB	MM 7.320, LT.	F	R1-1	30	30			6.25					X	X	1.00		14.0								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT 190' EAST AND ACROSS FROM POLE # 64 / 16	X								
EB	MM 7.353, RT.	A	R2-1	24	30			5.00					X	X	1.00		13.0								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ADJACENT TO POLE # VERT TEL / 10 / 21	X								
		A	VR-017	24	30								X												REMOVE THE EXISTING VR-017 SIGN BELOW THE R2-1 SIGN LOCATED ADJACENT TO POLE # VERT TEL / 10 / 21									
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>																																		