

TRAFFIC SIGN SUMMARY SHEET 1

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL								
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	P-1-A-N		P-1-C-O-M-P-O-S	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	7.60	9.00	10.80	14.60	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
NB	MM 0.000, LT.	J	R4-7	24	30			5.00					X	X	1.00											REPLACE SIGN AND POST ON THE SOUTH END OF THE ISLAND AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X						
		J	OM1-1	18	18			2.25					X													REPLACE SIGN ON THE SOUTH END OF THE ISLAND AND INSTALL BELOW THE KEEP RIGHT SIGN.	X						
SB	MM 0.003, LT.	K	R4-7	24	30			5.00					X	X	1.00											REPLACE SIGN AND POST ON THE NORTH END OF THE ISLAND AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X						
		K	OM1-1	18	18			2.25					X													REPLACE SIGN ON THE NORTH END OF THE ISLAND AND INSTALL NEW SIGN BELOW THE KEEP RIGHT SIGN	X						
NB	MM 0.024, RT.	A	W1-6	48	24			8.00							2.00											INSTALL NEW SIGN ON TWO POSTS 5 FT SOUTH OF LIGHT POLE # 10894. SIGN IS TO BE ORIENTED FACING SOUTHBOUND TRAFFIC.	X						
NB	MM 0.027, RT.	A	M3-1	24	12		PAID ON NEXT SHEET							X												REMOVE SIGN AND POST LOCATED 10 FT NORTH OF LIGHT POLE # 10894.							
		A	M1-6	30	24		PAID ON NEXT SHEET																			REMOVE SIGN LOCATED 10 FT NORTH OF LIGHT POLE # 10894 AND BELOW THE NORTH SIGN.							
		A	R14-1	24	18		PAID ON NEXT SHEET																			REMOVE SIGN LOCATED 10 FT NORTH OF LIGHT POLE #10894 & BELOW THE 127 SIGN.							
		A	R2-1	24	30		PAID ON NEXT SHEET																			REMOVE SIGN LOCATED 10 FT NORTH OF LIGHT POLE # 10894 AND BELOW THE TRUCK ROUTE SIGN.							
NB	MM 0.035, RT.	A	R2-1	24	30			5.00																		INSTALL NEW SIGN AND NEW POST 53 FT NORTH OF LIGHT POLE # 10894.	X						
NB	MM 0.035, RT.	A	R14-1	24	18			3.00																		INSTALL SIGN, LOCATED 53 FT NORTH OF LIGHT POLE # 10894, ON NEW POST NEXT TO THE SPEED LIMIT SIGN.	X						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB
				8	3			90				
SF	SF	EA	EA	EA	EA	FT	FT	FT	EA	LB		
30.50		8	6	3	6	90	70					

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: HES HSIP(4)
FILE NAME: I2k018wrk.dgn (I2k038)
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: JLS
BURLINGTON TRAFFIC SIGN SUMMARY SHEET 1 SHEET 87 OF 107