

TRAFFIC SIGN SUMMARY SHEET 2

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	REPLACE		REMOVE	POSTS	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
NB	MM 2.190, LT.	CD	D3-1	30	12			2.50																INSTALL ABOVE THE STOP SIGN		86				
							ROUTE 127 (W. LAKESHORE RD.)																							
SB	MM 2.192, LT.	F	TOWN SIGN	30	36																			REMOVE SIGN AND POST LOCATED 103 FT SOUTH AND ACROSS POLE #137.						
SB	MM 2.192, LT.	G	D3-1	60	12			5.00						2.00										INSTALL NEW SIGN ON 2 POSTS 103 FT SOUTH OF AND ACROSS POLE #137.		86				
SB	MM 2.201, LT.	F	VR-615	30	36			7.50																INSTALL NEW SIGN 53 FT SOUTH AND ACROSS POLE #137.		86				
NB	MM 2.220, RT.	A	M3-1	24	12			2.00																REPLACE SIGN AND POST LOCATED 47 FT NORTH OF POLE #137 BLACK TEXT AND BORDER ON A WHITE BACKGROUND	X					
		A	M1-6	30	24			5.00																REMOVE SIGN AND INSTALL NEW SIGN BELOW THE "NORTH" SIGN.			E-136C			
		A	M6-3	21	16			2.19																REMOVE EXISTING SIGN.						
SB	MM 2.222, LT.	F	M3-3	24	12			2.00																REPLACE SIGN AND POST AT SAME LOCATION, 61 FT SOUTH OF POLE #105A, BLACK TEXT AND BORDER ON A WHITE BACKGROUND	X					
		F	M1-6	30	24			5.00																REMOVE SIGN AND INSTALL NEW SIGN BELOW THE "SOUTH" SIGN.			E-136C			
		F	M5-1L	21	15			2.19																REPLACE SIGN AND INSTALL BELOW THE "127" SIGN, BLACK TEXT AND BORDER ON A WHITE BACKGROUND	X					
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>																														
								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								33.38		-6	8	3	5	75	65															

PROJECT NAME: STATEWIDE NORTHEAST REGION
 PROJECT NUMBER: HES HSIP(4)
 FILE NAME: I2k018wrk.dgn (I2k038)
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 COLCHESTER TRAFFIC SIGN SUMMARY SHEET 2 SHEET 92 OF 107
 PLOT DATE: 16-JUL-2012
 DRAWN BY: TDS
 CHECKED BY: JLS