STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILTON
WESTFORD RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 2.688, RT.	A	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE SIGN AND POST NEXT TO POLE # 2/57/22/4T.	X		
EB	MM 2.770, RT.	A	W1-4L	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 206 FT WEST OF DRIVE FOR HOUSE # 431.	X		
WB	MM 2.778, LT.	F	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE SIGN AND POST 95 FT EAST AND ACROSS THE CENTERLINE OF BROOKSIDE DRIVE .	X		
							(12) WHITE STEEL GUARDRAIL REFLECTORS																			REMOVE REFLECTORS INSIDE THE GUARDRAIL AND INSTALL NEW REFLECTORS EVERY 5 POSTS.			G-1
WB	MM 2.928, LT.	F	S3-1	36	36	FYG		9.00					X		X	2.00		14.0 ~~30~~ 14.0								REPLACE SIGN AND POST LOCATED 132 FT WEST OF DRIVE #460.	X		
WB	MM 3.000, LT.	F	W1-4L	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 243 FT WEST OF AND ACROSS FROM POLE # 291/40/2/82.	X		
										EA	EA	EA	EA 3	EA	EA 3		FT	FT ~~90~~	FT		LB	LB	LB	LB					
								SF 31.50	SF	EA 3				EA 3		EA 6	FT ~~90~~ 86			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: HES HSIP(4)

FILE NAME: 12k018wrk.dgn (12k038)
PROJECT LEADER: JLS
DESIGNED BY: NLA
MILTON 1TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: JLS
SHEET 95 **OF** 107