STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILTON
LAKE RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.00 (2.42)	SQUARE STEEL (in) lb/ft 2.50 (3.35)	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00 (7.60)	TUBULAR STEEL O/(in) lb/ft 3.50 (9.00)	TUBULAR STEEL O/(in) lb/ft 4.00 (10.80)	TUBULAR STEEL O/(in) lb/ft 5.00 (14.60)	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL IN SHSM	SIGN DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
WB	MM 0.741, LT.	F	R2-1	24	30			5.00					X		X	1.00		15								REMOVE EXISTING SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION 32 FT EAST POLE # 9 / 48X.	X		
EB	MM 0.858, RT.	A	W1-2L	30	30								X		X											REMOVE SIGN AND POST LOCATED 264 FT WEST OF POLE # 48-1.			
EB	MM 0.957, RT.	A	W1-1R	30	30			6.25								1.00		15								INSTALL SIGN AND POST 448 FT EAST OF POLE # 48-2.	X		
		A	W13-1P	18	18			2.25																		INSTALL BELOW THE TURN SIGN.	X		
WB	MM 0.976, LT.	E F	W1-8 W1-8	18 18	24 24			3.00 3.00								1.00		11.0 ~~15~~								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 871 FT EAST AND ACROSS POLE # 48-2 FT.	X		
WB	MM 0.991, LT.	E F	W1-8 W1-8	18 18	24 24			3.00 3.00								1.00		11.0 ~~15~~								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 786 FT SOUTH AND ACROSS POLE # 48-2 FT .	X		
WB	MM 1.006, LT.	E F	W1-8 W1-8	18 18	24 24			3.00 3.00								1.00		11.0 ~~15~~								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 707 FT EAST AND ACROSS POLE # 48-2 FT.	X		
WB	MM 1.021, LT.	E F	W1-8 W1-8	18 18	24 24			3.00 3.00								1.00		11.0 ~~15~~								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 628 FT EAST AND ACROSS POLE # 48-2 FT.	X		
								SF 37.50	SF	EA 2				EA 2		EA 6	FT ~~90~~ 74			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: HES HSIP(4)

FILE NAME: 12k018wrk.dgn (12k038) **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** JLS
MILTON 3 TRAFFIC SIGN SUMMARY SHEET 3 **SHEET** 101 **OF** 107