STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILTON
LAKE RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
WB	MM 1.036, LT.	E	W1-8	18	24			3.00								1.00		II.0 ~~15~~								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 549 FT EAST AND ACROSS POLE # 48-2 FT.	X		
		F	W1-8	18	24			3.00																				
WB	MM 1.055, LT.	F	W1-1L	30	30			6.25								1.00		15								INSTALL SIGN AND POST 274 FT WEST OF POLE # 9/ 40.	X		
WB		F	W13-1P	18	18			2.25																		INSTALL BELOW THE TURN SIGN.	X		
WB	MM 1.061, RT.	A	W1-2L	30	30								X		X											REMOVE SIGN AND POST LOCATED 126 FT WEST OF POLE # 9 / 40.			
WB	MM 1.141, LT.	F													X											REMOVE EMPTY POST LOCATED 179 FT EAST OF POLE # 9 / 40.			
EB	MM 1.201, RT.	A	W1-1L	30	30			6.25								1.00		15								INSTALL SIGN AND POST 496 FT EAST OF AND ACROSS FROM POLE # 9 / 40.	X		
		A	W13-1P	18	18			2.25																		INSTALL ADVISORY PLAQUE BELOW THE TURN SIGN.	X		
EB	MM 1.251, RT. TO MM 1.324, RT.	A B		6	8		(16) TYPE II - 6" x 8" WHITE DELINEATORS											72								INSTALL DELINEATORS BACK-TO-BACK ON 8 POSTS. PUT FIRST POST 760 FT EAST AND ACROSS POLE # 9/40, CONTINUING EAST. INSTALL 55 FT APART.		5	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

		NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60
		EA	EA	EA	EA	EA	~~1~~	EA	2		FT	FT ~~45~~	FT		LB	LB	LB	LB
16.0 DELINEATORS		SF 23.00	SF	EA ~~1~~ 2		EA 2		EA 3			FT ~~45~~			EA	LB			

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: HES HSIP(4)

FILE NAME: 12k018wrk.dgn (12k038) **PLOT DATE:** 19-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** JLS
MILTON 3 TRAFFIC SIGN SUMMARY SHEET 4 **SHEET** 102 **OF** 107