

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
										ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										350	350		CY	EARTH BORROW	203.30	EST.			
										1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			
										8	8		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
										8	8		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
										8	8		HR	TRUCK RENTAL	608.37	EST.			
										8	8		HR	LOADER RENTAL, TYPE I	608.40	EST.			
										562.5	562.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
										14	14		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
										481	481		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
										24	24		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
										275	275		HR	FLAGGERS	630.15	EST.			
										0.5	0.5		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
										1	1		LS	TRAFFIC CONTROL (STP HRRR(15))	641.10	-			
										750	750		LF	4 INCH YELLOW LINE	646.21	7.12			
										100	100		LF	8 INCH WHITE LINE	646.22	-			
										96	96		LF	24 INCH STOP BAR	646.26	-			
										63	63		EACH	LETTER OR SYMBOL	646.30	-			
										35	35		LB	SEED	651.15	EST.			
										35	35		LB	FERTILIZER	651.18	EST.			
										0.7	0.7		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
										1.75	1.75		TON	HAY MULCH	651.25	EST.			
										17.5	17.5		CY	TOPSOIL	651.35	EST.			
										350	350		SY	TEMPORARY EROSION MATTING	653.20	EST.			
										1112.85	1112.85		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
										2910	2910		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
										162	162		EACH	REMOVING SIGNS	675.50	-			
										15	15		EACH	DELINEATOR WITH STEEL POST	676.10	-			

PROJECT NAME: STATEWIDE SOUTHWEST REGION  
PROJECT NUMBER: STP HRRR(15)

FILE NAME: i12k024frm.dgn  
PROJECT LEADER: JLS  
DESIGNED BY: MBL  
QUANTITY SHEET

PLOT DATE: 06-AUG-2012  
DRAWN BY: MBL  
CHECKED BY: NA  
SHEET 10 OF 90