STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		F	W16-7P	30	18			3.75	FYG				X													REPLACE THE EXISTING W16-7P SIGN BELOW THE S1-1 SIGN LOCATED 310' SOUTH OF POLE # 47 / 67.	X		
SB	MM 0.778, LT.	F	W3-3	30	30								X													REMOVE THE W3-3 SIGN FROM POLE # 47 / 67.			
NB	MM 0.855, RT.	A	S1-1	36	36			9.00	FYG				X		X	2.00		30								REPLACE THE EXISTING S1-1 LOCATED ACROSS FROM POLE # 549 / 68.	X		
		A	W16-7P	30	18			3.75	FYG				X													REPLACE THE EXISTING W16-7P SIGN BELOW THE S1-1 SIGN LOCATED ACROSS FROM POLE # 549 / 68.	X		
SB	MM 0.858, LT.	F	S1-1	36	36			9.00	FYG				X		X	0 ~~2.00~~		0 ~~30~~								REPLACE THE EXISTING S1-1 LOCATED 15' NORTH OF POLE # 549 / 68.	X		
		F	W16-7P	30	18			3.75	FYG				X													REPLACE THE EXISTING W16-7P SIGN BELOW THE S1-1 SIGN LOCATED 15' NORTH OF POLE # 549 / 68.	X		
SB	MM 0.920, LT.	F	S1-1	30	30								X		X											REMOVE THE EXISTING S1-1 SIGN AND POST LOCATED 48' NORTH OF POLE # 1 / 50 / 173T / 50.			
			W16-9P	24	12		AHEAD						X													REMOVE THE EXISTING W16-9P SIGN BELOW THE S1-1 SIGN LOCATED 48' NORTH OF POLE # 1 / 50 / 173T / 50.			
NB	MM 0.929, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00							X	1.00		15								INSTALL A NEW R2-1 SIGN ON A NEW POST. LOCATE IT 90' NORTH AND ACROSS FROM POLE # 1 / 50 / 173T / 50.	X		
			S5-2	18 ~~24~~	24 ~~30~~		END SCHOOL ZONE	3.00 ~~5.00~~					2 ~~X~~				WRONG SIZE SIGN INSTALLED - NOTICED DURING FINAL INSPECTION. CRRECT SIZE INSTALLED									REPLACE THE EXISTING S5-2 SIGN BELOW THE NEW R2-1 SIGN LOCATED 90' NORTH AND ACROSS FROM POLE # 1 / 50 / 173T / 50.	X		
SB	MM 0.933, LT.	F	S4-3P	24	8		SCHOOL	1.33	FYG				X	X												REPLACE THE EXISTING SIGN AND RETAIN THE POST LOCATED 40' SOUTH OF POLE # 70 / 51.	X		
										EA	EA	EA	EA 10	EA 1	EA 4			FT 75					LB	LB	LB	LB				
								SF 40.58	SF	EA 10				EA 5		EA 5		FT ~~75~~ 38.17					EA	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA