STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		F	R2-1	24	30		SPEED LIMIT 25 STRAIGHTEN POST			X																	RETAIN THE EXISTING SIGN AND POST LOCATED 40' SOUTH OF POLE # 70 / 51.			
		F	S4-1P	24	10		6:00 AM TO 4:30 PM			X																	RETAIN THE EXISTING SIGN AND POST LOCATED 40' SOUTH OF POLE # 70 / 51.			
SB	MM 0.969, LT.												I		X												REMOVE POST LOCATED 148' NORTH OF POLE # 70 / 51.			
SB	MM 0.970, LT.	F	S1-1	36	36	FYG		9.00								2.00		30									INSTALL A NEW S1-1 SIGN AND POST LOCATED 153' NORTH OF POLE # 70 / 51.	X		
			S4-3P	36	12	FYG	SCHOOL	3.00																			INSTALL A NEW S4-3P SIGN BELOW THE S1-1 SIGN LOCATED 153' NORTH OF POLE # 70 / 51.	X		
SB	MM 1.015, LT.	F	S4-5	36	36	FYG	SCHOOL SPEED LIMIT 25	9.00								2.00		30									INSTALL A NEW S4-5 SIGN AND POST. LOCATE ITACROSS FROM POLE # 30A / 53A.	X		
SB	MM 1.150, LT.	F	S1-1	30	30								X		X												REMOVE THE EXISTING S1-1 SIGN AND POST LOCATED 75' SOUTH AND ACROSS FROM POLE # 57 / 213 / 26.			
			W16-9P	24	12		AHEAD						X														REMOVE THE EXISTING W16-9P SIGN BELOW THE S1-1 SIGN LOCATED 75' SOUTH AND ACROSS FROM POLE # 57 / 213 / 26.			
SB	MM 1.302, LT.	F	S4-3P	24	8		SCHOOL						X		X												REMOVE THE EXISTING S4-3P SIGN AND POST LOCATED 37' NORTH OF POLE # 23.			
		F	R2-5A	24	30		REDUCED SPEED AHEAD						X														REMOVE THE EXISTING R2-5A SIGN BELOW THE S4-3P SIGN LOCATED 37' NORTH OF POLE # 23.			
SB	MM 1.416, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00								1.00		15									INSTALL A NEW R2-1 SIGN AND POST. LOCATE IT ADJACENT TO BUSINESS SIGN FOR STORE.			
										EA 2	EA	EA	EA 4 5	EA	EA 3			FT 75							LB					
								SF 26.00	SF	EA 67				EA 3		EA 5		FT 75 67.08		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: I2k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA