STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.534, RT.	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING R2-1 SIGN AND POST LOCATED 10' SOUTH OF POLE # 66 / 213 / 18.			
NB	MM 1.545, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00								1.00		15								INSTALL A NEW R2-1 SIGN AND POST. LOCATE IT 50' NORTH OF POLE # 66 / 213 / 18.	X		
NB	MM 1.614, RT.	A	W2-2L	30	30			6.25								1.00		15								INSTALL A NEW W2-2 L SIGN AND POST. LOCATE IT 75' SOUTH OF POLE # 69 / 15X.	X		
		A	W16-8P	30	8		Houghton Ln	1.67																		INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 75' SOUTH OF POLE # 69 / 15X.		12	
SB	MM 1.638, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 53' NORTH AND ACROSS FROM POLE # 69 / 15X.	X		
NB	MM 1.663, RT.	C	W1-7	48	24			8.00								2.00		30								INSTALL A NEW W1-7 SIGN AND POST. LOCATE IT 40' SOUTH OF POLE # 1/0/1B/70/1-8/21.	X		
NB	MM 1.684, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST. LOCATE IT 75' NORTH OF POLE # 1/0/1B/70/1-8/21.	X		
SB	MM 1.695, LT.	F	W2-2R	30	30			6.25								1.00		15								INSTALL A NEW W2-2 R SIGN AND POST. LOCATE IT 64' SOUTH AND ACROSS FROM POLE # 70 1/2 /14.	X		
		F	W16-8P	30	8		Houghton Ln	1.67																		INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 64' SOUTH AND ACROSS FROM POLE # 70 1/2 /14.		12	
										EA 3			EA 3	EA 3				FT 105											
								SF 38.84	SF	EA 3			EA 3			EA 7		FT ~~105~~ 92.83		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA