STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.777, RT.	A	W2-2R	30	30			6.25								1.00		15									INSTALL A NEW W2-2 R SIGN AND POST. LOCATE IT 15' SOUTH OF POLE # 11X / 72.	X		
		A	W16-8P	30	8			1.67																			INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 15' SOUTH OF POLE # 11X / 72.		12	
NB	MM 1.803, RT.	A B	D3-1	48	12			4.00					X														REPLACE THE EXISTING D3-1 SIGN OVER THE R1-1 SIGN LOCATED 115' NORTH OF POLE # 11X / 72.		12	
		D	R1-1	30	30			6.25					X		X	1.00		15									REPLACE THE EXISTING R1-1 SIGN AND POST LOCATED 115' NORTH OF POLE # 11X / 72.	X		
NB	MM 1.830, RT.												X		X												REMOVE EXISTING POST LOCATED ADJACENT TO POLE # 213 / 11 / 2.			
SB	MM 1.860, LT.	F	W2-2L	30	30			6.25								1.00		15									INSTALL A NEW W2-2 R SIGN AND POST. LOCATE IT 15' SOUTH OF POLE # 11X / 72.	X		
		F	W16-8P	30	8			1.67																			INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 15' SOUTH OF POLE # 11X / 72.		12	
NB	MM 1.860, RT.	A	R2-1	24	30			5.00								1.00		15									INSTALL A NEW R2-1 SIGN AND POST. LOCATE IT 160' NORTH OF POLE # 213 / 11 / 2.	X		
							WILLOW RD.																							
EB	MM 0.030, RT.	GH	R1-1	36	12			3.00					X														INSTALL D3-1 ABOVE R1-1 ON SAME POST. RELOCATE 20' WEST OF EXISTING R1-1 LOCATION.		12	
		F	R1-1	30	30			6.25					X		X	1.00		15									REPLACE EXISTING R1-1 SIGN AND POST. RELOCATE 20' WEST OF EXISTING LOCATION.	X		
WB	MM 0.050, LT.	A	R2-1	24	30			5.00					X		X	1.00		15									REMOVE EXISTING POST. INSTALL A NEW R2-1 SIGN AND POST. LOCATE IT 260' EAST OF POLE # 25 / 25.	X		
								EA	EA	EA	EA	EA	EA				FT	FT	FT		LB	LB	LB	LB					
								SF 45.34	SF	EA ~~3~~ 6				EA 4		EA 6	FT ~~90~~ 80.83			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: I2k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
BENNINGTON TRAFFIC SIGN SUMMARY SHEET 6
SHEET 19 OF 90