STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.100, LT.	A	R2-1	24	30		SPEED LIMIT 35						X 0		X											REMOVE EXISTING SIGN AND POST LOCATED 10' WEST OF POLE # 25 / 25.	X		
							HOUGHTON LN.																						
EB	MM 0.010, RT.	GH	D3-1	48	12		Houghton Ln	4.00					X			2.00		30								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO NEWLY INSTALLED R1-1 LOCATED 25' WEST OF EXISTING R1-1 LOCATION.		12	
EB	MM 0.010, RT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		15								REMOVE EXISTING R1-1 SIGN AND POST. INSTALL A NEW R1-1 SIGN AND POST 25' WEST OF EXISTING LOCATION.	X		
WB	MM 0.029, LT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED 10' WEST AND ACROSS FROM POLE # 2132 / 1 / 1-8 / 1.	X		
		A	TOWN SIGN	24	24		HEARING IMPAIRED AREA						X													REMOVE THE EXISTING TOWN SIGN BELOW THE R2-1 SIGN LOCATED 10' WEST AND ACROSS FROM POLE # 2132 / 1 / 1-8 / 1.			
EB	MM 0.066, RT.	F	W3-1	30	30			6.25								1.00		15								INSTALL A NEW W3-1 SIGN AND POST. LOCATE IT 15' WEST OF POLE # 181> / 1-8.	X		
										EA	EA	EA	EA 4	EA	EA 3		FT	FT 75	FT		LB	LB	LB	LB					
								SF 21.50	SF	EA 4				EA 3		EA 5	FT ~~75~~ 61.0			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA