STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

BENSON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.673, RT.	A	W2-7L	36	36			9.00								2.00		30								INSTALL NEW SIGN AND POSTS. LOCATE IT 296' WEST OF POST # 28 / 33.	X		
		A	W16-8aP	48	15			5.00																		INSTALL NEW SIGN BELOW THE W1-2MaR SIGN. LOCATED 296' WEST OF POST # 28 / 33.		11	
WB	MM 1.700, LT.	F	R2-1	24	30			5.00								1.00		15								INSTALL NEW SIGN AND POST. LOCATE IT 153' WEST AND ACROSS FROM POLE # 28 / 33.	X		
EB	MM 1.714, RT.	A	D1-1	72	12			6.00								2.00		30								INSTALL NEW SIGNS AND POSTS. LOCATE IT 80' WEST OF POLE # 28 / 33.		11	
		A	D1-1	72	12			6.00																		INSTALL NEW SIGNS AND POSTS. LOCATE IT 80' WEST OF POLE # 28 / 33.		11	
WB	MM 1.729, LT.	F	M3-4	24	12			2.00								1.00		15								INSTALL NEW SIGNS AND POST. LOCATED ACROSS FROM POLE # 28 / 33. BLACK TEXT & BORDER ON A WHITE BACKGROUND	X		
		F	M1-5	30	24			5.00																		INSTALL NEW SIGNS AND POST. LOCATE IT ACROSS FROM POLE # 28 / 33. BLACK TEXT & BORDER ON A WHITE BACKGROUND			E-136C
WB	MM 1.729, LT.	E	D1-1	54	8								X		X											REMOVE EXISTING ASSEMBLY LOCATED 106' EAST AND ACROSS FROM POLE # 28 / 33.			
		E	D1-1	54	8								X													REMOVE EXISTING ASSEMBLY LOCATED 106' EAST AND ACROSS FROM POLE # 28 / 33.			
		E	D1-1	54	8								X													REMOVE EXISTING ASSEMBLY LOCATED 106' EAST AND ACROSS FROM POLE # 28 / 33.			
		E	M1-6	30	24								X													REMOVE EXISTING ASSEMBLY LOCATED 106' EAST AND ACROSS FROM POLE # 28 / 33.			
		E	M6-2	21	15								X													REMOVE EXISTING ASSEMBLY LOCATED 106' EAST AND ACROSS FROM POLE # 28 / 33.			
							MM						X																
										EA	EA	EA	EA 5	EA	EA 1			FT	FT 90	FT		LB	LB	LB	LB					
								SF 38.00	SF	EA ~~5~~ 6				EA 1		EA 6		FT ~~90~~ 85.0			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA