













# TRAFFIC SIGN SUMMARY SHEET 4

## BENSON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					EXISTING POST	NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS  SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN			REMOVE	FOUNDAION	lb/ft		lb/ft		DETAIL IN SHSM			DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER	
																			1.75	2.00	2.50	3.00						3.50
WB	MM 1.750, LT.	EF	D3-1	60	12		<b>Sunset Lake Rd</b>	5.00															REPLACE EXISTING SIGN LOCATED ABOVE THE R1-1 SIGN 111' EAST AND ACROSS FROM POLE # 28 / 33.		11			
		H	R1-1	30	30			6.25						X	X	1.00	15						REPLACE EXISTING SIGN AND POST LOCATED 111' EAST AND ACROSS FROM POLE # 28 / 33.	X				
WB	MM 1.768, LT.	EF	W1-6	48	24			8.00								2.00	30						INSTALL NEW SIGN AND POST. LOCATE IT 85' EAST AND ACROSS FROM POLE # A / 34-1A.	X				
WB	MM 1.768, LT.	F	D1-1	54	8									X	X								REMOVE EXISTING ASSEMBLY LOCATED 85' WEST AND ACROSS FROM POLE # A / 34-1A.					
		F	D1-1	54	8									X									REMOVE EXISTING ASSEMBLY LOCATED 85' WEST AND ACROSS FROM POLE # A / 34-1A.					
		F	D1-1	54	8									X									REMOVE EXISTING ASSEMBLY LOCATED 85' WEST AND ACROSS FROM POLE # A / 34-1A.					
		F	M1-6	30	24									X									REMOVE EXISTING ASSEMBLY LOCATED 85' WEST AND ACROSS FROM POLE # A / 34-1A.					
		F	M6-2	21	15									X									REMOVE EXISTING ASSEMBLY LOCATED 85' WEST AND ACROSS FROM POLE # A / 34-1A.					
EB	MM 1.772, RT.	AB	D3-1	60	12		<b>Howard Hill Rd</b>	5.00															REPLACE EXISTING SIGN ABOVE THE R1-1 SIGN LOCATED 63' WEST OF POLE # A / 34-1A.		11			
		D	R1-1	30	30			6.25						X	X	1.00	15						REPLACE EXISTING SIGN AND POST LOCATED 63' WEST OF POLE # A / 34-1A.	X				
WB	MM 1.784, LT.	A	D1-1	72	12			6.00								2.00	30						INSTALL NEW SIGNS AND POSTS. LOCATE IT ACROSS FROM POLE # A / 34-1A.		11			
		A	D1-1	72	12			6.00															INSTALL NEW SIGNS AND POSTS. LOCATE IT ACROSS FROM POLE # A / 34-1A.		11			
EB	MM 1.800, RT.	A	M3-2	24	12			2.00								1.00	15						INSTALL NEW SIGNS AND POST. LOCATE IT 15' EAST OF POLE # A / 34-1A. BLACK TEXT & BORDER ON A WHITE BACKGROUND	X				
		A	M1-5	30	24			5.00															INSTALL NEW SIGNS AND POST. LOCATE IT 15' EAST OF POLE # A / 34-1A.				E-136C	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB
			9	10	3			105				
SF	SF	EA	EA	EA	EA	FT	FT	FT	EA	LB		
49.50		9	10	3	7	105	105	95.75				

**PROJECT NAME:** STATEWIDE SOUTHWEST REGION  
**PROJECT NUMBER:** STP HRRR(15)  
**FILE NAME:** I2k024frm.dgn  
**PROJECT LEADER:** JLS  
**DESIGNED BY:** NLA  
**PLOT DATE:** 06-AUG-2012  
**DRAWN BY:** TDS  
**CHECKED BY:** NLA  
**SHEET** 25 **OF** 90