STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

BENSON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 1.997, LT.	F	W1-2	30	30								2 ~~X~~		X											REMOVE EXISTING SIGN AND POST LOCATED 876' EAST AND ACROSS FROM POLE # 34-2.			
EB	MM 2.162, RT.	A	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 1750' EAST OF POLE # 34-2.	X		
WB	MM 2.162, LT.	F	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 1750' EAST AND ACROSS FROM POLE # 34-2.	X		
WB	MM 2.318, LT. TO MM 2.358, LT.	EF		6	8		(6) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (6) BACK-TO-BACK 70' APART ON 3 POSTS, INSTALL FIRST POST 1725' WEST OF POLE # 241-2.		4	
EB	MM 2.645, RT.	A	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED ACROSS FROM POLE # 241-2.	X		
WB	MM 2.162, LT.	F	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED ADJACENT TO POLE # 241-2.	X		
WB	MM 2.853, LT. TO MM 2.893, LT.	AB		6	8		(6) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (6) BACK-TO-BACK 70' APART ON 3 POSTS, INSTALL FIRST POST 153' WEST OF POLE # 236.		4	
EB	MM 2.960, RT.	A	W1-1L	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 412' EAST OF POLE # 236.	X		
		A	W13-1	18	18			2.25					0 ~~X~~													REPLACE EXISTING SIGN BELOW THE W1-1 SIGN LOCATED 412' EAST OF POLE # 236.	X		
										EA	EA	EA	EA 7	EA	EA 6		FT	FT 75	FT		LB	LB	LB	LB					
								SF 28.50	SF	EA 7				EA 6		EA 5	FT ~~75~~ 68.0			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BENSON TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 27 **OF** 90