STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

CASTLETON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.720, RT.	AB	D3-1	36	12		Belgo Rd	3.00																		INSTALL NEW SIGN ABOVE R1-1 SIGN.		12	
		D	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 26' SOUTH OF POLE # 48 / 68 / NET / 68.	X		
NB	MM 0.753, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 150' NORTH OF POLE # 48 / 68 / NET / 68.	X		
SB	MM 1.124, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 6' SOUTH AND ACROSS FROM POLE # 8 / NET / 18.	X		
SB	MM 1.286, LT.	F	W11-7	30	30								0 X		X											REMOVE SIGN AND POST LOCATED 240' SOUTH AND ACROSS FROM POLE # 82.			
NB	MM 1.306, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 132' SOUTH OF POLE # 82.	X		
NB	MM 1.656, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 26' NORTH AND ACROSS FROM POLE # 87.	X		
SB	MM 1.656, LT.	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 26' NORTH OF POLE # 87.	X		
										EA	EA	EA	EA ~~7~~6	EA	EA 7		FT	FT 90	FT		LB	LB	LB	LB					
								SF 34.25	SF	EA ~~7~~6				EA 7		EA 6	FT ~~90~~ 82.58			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(15)

FILE NAME: 12k024frm.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA