STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

**SOUTH ST.
BENNINGTON**

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.763, LT.	FG	D3-1	54	12		Brookside Apts	4.50					X		X	2.00		30								REMOVE SIGN AND POST AT THE NORTHWEST CORNER OF BROOKSIDE APTS AND SOUTH ST AND INSTALL NEW SIGN ON 2 POSTS ABOUT 8 FT WEST OF THE CURRENT LOCATION.		53	
SB	MM 2.763, LT.	F	W11-2	30	30	FYG		6.25								1.00		15								INSTALL NEW SIGN AT THE NORTHWEST CORNER OF BROOKSIDE APTS AND SOUTH ST AT THE LOCATION WHERE THE EXISTING BROOKSIDE STREET NAME SIGN WAS.	X		
		F	W16-7P	24	12	FYG		2.00																		INSTALL NEW SIGN BELOW THE NEW PEDESTRIAN SIGN AT THE NORTHWEST CORNER OF BROOKSIDE APTS AND SOUTH ST.	X		
SB	MM 2.763, LT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		15								REMOVE SIGN AND POST AT THE SOUTHWEST CORNER OF BROOKSIDE APTS AND SOUTH ST AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
SB	MM 2.796, RT.	B	W11-2	30	30	FYG		6.25								1.00		15								INSTALL NEW SIGN AND POST 74 FT SOUTH AND ACROSS POLE # 5 49.	X		
		B	W16-9P	24	12	FYG	AHEAD	2.00																		INSTALL BELOW THE NEW PEDESTRIAN SIGN.	X		
SB	MM 2.926, LT.	FG	D3-1	42	12		Franklin Ln	3.50					X		X	1.00		15			REINSTALLED POST DUE TO HEIGHT CONCERNS: PAY ADDITIONAL 8'					REMOVE SIGN AND POST AT FRANKLIN AND SOUTH ON THE NORTWEST CORNER AND INSTAL NEW SIGN ON 2 POSTS AT SAME LOCATION.		53	
		F	R6-1	36	12		ONE WAY	3.00																		INSTALL NEW SIGNS BACK-TO-BACK BELOW FRANKLIN ST NAME SIGN AT FRANKLIN AND SOUTH ON THE NORTWEST CORNER. INSTALL ON POST CLOSEST TO US7.	X		
		E	R6-1	36	12		ONE WAY ONE WAY	3.00																		INSTALL NEW SIGNS BACK-TO-BACK BELOW FRANKLIN ST NAME SIGN AT FRANKLIN AND SOUTH ON THE NORTWEST CORNER. INSTALL ON POST CLOSEST TO US7.	X		
										EA	EA	EA	EA 3	EA	EA 3		FT	FT 90	FT					LB	LB	LB	LB					
								SF 36.75	SF				EA 3		EA 3	EA 6		FT ~~90~~ 71.25		EA				LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
BENNINGTON I TRAFFIC SIGN SUMMARY SHT 2
SHEET 55 **OF** 90