STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

SOUTH ST.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							FRANKLIN LN.																						
EB	MM 0.024, LT.	A	R5-1	30	30			0 ~~6.25~~								0 ~~1.00~~		15			PROPERTY OWNER DOES NOT WANT THESE NEXT TO HIS BUILDING					INSTALL NEW SIGN ON THE SOUTH SIDE OF FRANKLIN LN 37 FT EAST AND ACROSS POLE # 4.	X		
		C	R6-1	36	12			0 ~~3.00~~													THERE IS NOWHERE ELSE TO PUT THEM SIGNS NOT INSTALLED					INSTALL NEW SIGN BELOW THE NEW DO NOT ENTER SIGN ON FRANKLIN LN 37 FT EAST AND ACROSS POLE # 4. INSTALL BACK-TO-BACK WITH CORRESPONDING ONEW WAY SIGN	X		
		D	R6-1	36	12			0 ~~3.00~~																		INSTALL NEW SIGN BELOW THE NEW DO NOT ENTER SIGN ON FRANKLIN LN 37 FT EAST AND ACROSS POLE # 4. INSTALL BACK-TO-BACK WITH CORRESPONDING ONEW WAY SIGN	X		
WB	MM 0.027, RT.	E	R5-1	30	30			6.25					X		X	1.00		15								REMOVE SIGN AND POST ON NORTH SIDE OF FRANKLIN LN 21 FT EAST OF POLE #4 AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
WB	MM 0.045, RT.	E	R2-1	24	30			5.00								1.00		15								INSTALL NEW SIGN ON THE NORTH SIDE OF FRANKLIN LN 10 FT EAST OF POLE #3 2.	X		
WB	MM 0.047, RT.	E	R2-1	24	30								X		X						REINSTALLED POST DUE TO HEIGHT CONCERNS: PAY ADDITIONAL 8'					REMOVE SIGN LOCATED ON POLE # 3 2 ON NORTH SIDE OF FRANKLIN LN 84 FT EAST OF POLE # 3 2.			
										EA 2	EA	EA	EA	EA 2	EA		FT 45		FT		LB	LB	LB	LB					
								SF ~~23.50~~ 11.25	SF	EA 2				EA 2		EA 3	FT ~~45~~ 26.25			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
BENNINGTON I TRAFFIC SIGN SUMMARY SHT 3

PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 56 **OF** 90