STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MATTESON RD.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.000, RT.	CD	D3-1	48	12		Matteson Rd	4.00					X		X	2.00		30								REPLACE EXISTING SIGN ON 2-POSTS LOCATED NORTHEAST OF MATTESON RD AND RICE LN INTERSECTION ADJACENT TO STOP SIGN		53	
NB	MM 0.000, RT.	AB	D3-1	30	12		Rice Ln	2.50					X		X											REPLACE EXISTING SIGN INSTALL ABOVE MATTESON RD SIGN WITH 12" BRACKET LOCATED NORTHEAST OF MATTESON RD & RICE LN INTERSECTION		53	
		D	R1-1	36	30		STOP	6.25					X		X	1.00		15								REPLACE EXISTING SIGN & POST LOCATED AT NORTHEAST CORNER OF MATTESON RD & RICE LN INTERSECTION	X		
NB	MM 0.021, RT.	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST 85 FT SOUTH OF AND ACROSS FROM POLE # 7/1/823/2.	X		
SB	MM 0.071, LT.	F	W1-10R	36	36			9.00					X		X	2.00		30								REPLACE EXISTING SIGN AND POST 180 FT NORTH OF POLE # 7/1/823/2.	X		
NB	MM 0.103, RT.	A	S1-1	30	30	FYG		6.25								1.00		15								INSTALL NEW SIGN AND POST 90 FT NORTH OF POLE # 9/823/9.	X		
		A	S4-3P	24	8	FYG	SCHOOL	1.33																		INSTALL NEW PLAQUE BELOW S1-1 SIGN ON THE SAME POST.	X		
NB	MM 0.155, RT.	A	W1-1R	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 35 FT NORTH OF DRIVEWAY OR 69 FT NORTH OF AND ACROSS FROM POLE #7/5/822.	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST.	X		
SB	MM 0.165, LT.	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SIGN AND POST 37 FT SOUTH OF POLE # 823 / 6.			
SB	MM 0.178, LT.	F	S5-2	24	30		END SCHOOL ZONE	5.00					~~X~~ 0		X	1.00		15								REPLACE EXISTING SIGN AND POST 32 FT NORTH OF POLE # 823/6.	X		
		F	R2-1	24	30		SPEED LIMIT 35	5.00																		INSTALL NEW SIGN ABOVE S5-2 SIGN ON SAME POST 32 FT NORTH OF POLE # 823/6	X		
NB	MM 0.178, RT.	A	S4-3P	24	8	FYG	SCHOOL	1.33								1.00		15								INSTALL NEW SIGN AND POST ACROSS FROM END SCHOOL ZONE ASSEMBLY. 32 FT NORTH OF AND ACROSS FROM POLE # 823/6	X		
										EA	EA	EA	EA ~~8~~6	EA	EA ~~8~~6			FT 150	FT		LB	LB	LB	LB					
								SF ~~54.16~~ 55.41	SF	EA ~~8~~6				EA ~~8~~6		EA 10		FT ~~150~~ 118.75		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042) **PLOT DATE:** 06-AUG-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
BENNINGTON 2 TRAFFIC SIGN SUMMARY SHT 1 **SHEET** 58 **OF** 90