STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MATTESON RD.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.372, LT.	F	S4-3P	24	8	FYG	SCHOOL	1.33					X		X	1.00		15								REPLACE EXISTING SIGN AND POST 100 FT NORTH OF AND ACROSS FROM POLE # 13/823/14.	X		
		F	R2-1	24	30		SPEED LIMIT 25	5.00					X													REPLACE EXISTING SIGN BELOW S4-3P SIGN ON THE SAME POST.	X		
SB	MM 0.377, LT.	H	R1-1	30	30		STOP	6.25 ~~5.00~~					X		X											REPLACE EXISTING SIGN AND POST AT SOUTHWEST CORNER OF MATTESON RD AND HARLAN RD INTERSECTION.			
NB	MM 0.382, RT.	C	W1-7	48	24		⟷	8.00					X		X	2.00		30								REPLACE EXISTING SIGN AND POST ACROSS FROM MATTESON RD AND HARLAND RD INTERSECTION.	X		
SB	MM 0.382, LT.	E	D3-1	36	12		Harlan Rd	3.00					X		X											REPLACE EXISTING SIGN . INSTALL ABOVE MATTESON RD SIGN WITH 12" BRACKET LOCATE AT THE NORTHWEST CORNER OF MATTESON RD AND HARLAN RD INTERSECTION.		53	
SB	MM 0.382, LT.	H	D3-1	48	12		Matteson Rd	4.00					X			2.00		30								REPLACE EXISTING SIGN INSTALL ON 2-POSTS AT NORTHWEST CORNER OF MATTESON RD AND HARLAN RD INTERSECTION ADJACENT TO R1-1		53	
SB	MM 0.395, LT.	A	S1-1	30	30	FYG		6.25								1.00		15								INSTALL NEW SIGN AND POST 50 FT NORTH OF POLE # 823/207/4. JUST NORTH OF THE INTERSECTION OF HARLAN RD AND MATTESON RD	X		
		A	S4-3P	24	8	FYG	SCHOOL	1.33																		INSTALL NEW PLAQUE BELOW S1-1 SIGN ON THE SAME POST.	X		
										EA	EA	EA	EA 6	EA	EA 4			FT	FT 90	FT			LB	LB	LB	LB				
								SF ~~33.91~~ 35.16	SF	EA 6				EA 4		EA 6		FT ~~90~~ 85.17			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA