STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 1

**PARK ST.**
**BENNINGTON**

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK | SIGN DETAIL DETAIL IN SHSM | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NB | MM 0.009, RT. | A | S1-1 | 36 | 36 | FYG | | 9.00 | | | | | | | | 2.00 | | 30 | | | | | | | | INSTALL NEW SIGN AND POST 100 FT SOUTH OF POLE #17. | X | | |
| | | A | S4-3P | 24 | 8 | FYG | | 1.33 | | | | | | | | | | | | | | | | | | INSTALL BELOW THE NEW SCHOOL SIGN LOCATED 100 FT SOUTH OF POLE # 17. | X | | |
| SB | MM 0.010, LT. | F | R3-9dP | 30 | 12 | | | 2.50 | | | | | | | | 1.00 | | 15 | | | | | | | | INSTALL NEW SIGN 48 FT SOUTH OF AND ACROSS FROM POLE #17. | X | | |
| SB | | F | R8-3 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | INSTALL BELOW THE NEW END SIGN LOCATED 48 FT SOUTH OF AND ACROSS POLE #17. | X | | |
| NB | MM 0.019, RT. | A | TOWN SIGN | 24 | 30 | | | 5.00 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION 48 FT SOUTH OF POLE #17. | | 53 | |
| NB | MM 0.035, RT. | A | S1-1 | 36 | 36 | | | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST LOCATED 37 FT NORTH OF POLE #17. | | | |
| | | A | W16-4P | 30 | 24 | | | | | | | | X | | | | | | | | | | | | | REMOVE SIGN BELOW THE SCHOOL SIGN LOCATED 37 FT NORTH OF POLE #37. | | | |
| SB | MM 0.035, LT. | F | VR-345 | 12 | 18 | | | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST LOCATED 26 FT NORTH POLE #18. | | | |
| | | F | VR-922 | 36 | 30 | | | 7.50 | | | | | | | | 1.00 | | 15 | | | | | | | | INSTALL SIGN AND POST 37 FT NORTH OF AND ACROSS FROM POLE #17. | | | E-145A |
| NB | MM 0.061, RT. | A | TOWN SIGN | 12 | 18 | | | | | | | | 0 ~~X~~ | | 0 ~~X~~ | | | | | | | | | | | REMOVE SIGN AND POST LOCATED 26 FT NORTH POLE #18. | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | EA | EA | EA | EA | EA | EA | | FT | FT | FT | | | | | LB | LB | LB | LB | | |
| | | | | | | | | | | | | | ~~5~~ 4 | | 4 | | | 75 | | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | | | | EA | EA | FT | | | | EA | LB | | | | | | | | |
| | | | | | | | | 29.33 | | ~~5~~ 4 | | | | 4 | 5 | ~~75~~ 51.49 | | | | | | | | | | | | | |

**PROJECT NAME:** STATEWIDE SOUTHWEST REGION
**PROJECT NUMBER:** HES HSIP(6)

**FILE NAME:** I2k024frm.dgn (I2k042) **PLOT DATE:** 06-AUG-2012
**PROJECT LEADER:** JLS **DRAWN BY:** TDS
**DESIGNED BY:** NLA **CHECKED BY:** NLA
BENNINGTON 3 TRAFFIC SIGN SUMMARY SHT I **SHEET** 63 **OF** 90