STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

PARK ST.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL IN SHSM	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		A	TOWN SIGN	24	24		CLICK IT OR TICKET						~~X~~ 0														REMOVE SIGN LOCATED 26 FT NORTH POLE #18.			
NB	MM 0.061, RT.	A	R3-9cP	30	12		BEGIN	2.50								1.00		15								INSTALL NEW SIGN AND POST 26 FT NORTH OF POLE #18.	X		
		A	R8-3	24	24		R	4.00																		INSTALL NEW SIGN BELOW THE BEGIN SIGN LOCATED 26 FT NORTH OF POLE #18.	X		
NB	MM 0.078, RT.	A	vr-345	12	18		NO PARKING HERE TO CORNER						X		X											REMOVE SIGN AND POST LOCATED 63 FT SOUTH OF POLE # 19.			
		A	R3-9dP	30	12		END	2.50																		INSTALL NEW SIGN AND POST 63 FT SOUTH OF POLE # 19.	X		
		A	R8-3	24	24		R	4.00																		INSTALL NEW SIGN BELOW THE NEW END SIGN LOCATED 63 FT SOUTH OF POLE #19.	X		
SB	MM 0.080, LT.	F	TOWN SIGN	12	18		NO PARKING						X		X											REMOVE SIGN AND POST LOCATED 53 FT SOUTH OF AND ACROSS FROM POLE # 19.			
SB	MM 0.080, LT.	F	R3-9cP	30	12		BEGIN	2.50								1.00		15								INSTALL NEW SIGN AND POST 53 FT SOUTH OF AND ACROSS FROM POLE # 19.	X		
		F	R8-3	24	24		R	4.00																		INSTALL NEW SIGN BELOW THE NEW BEGIN SIGN.	X		
								SF 19.50	SF	EA	EA	EA	EA ~~3~~2	EA	EA 2	EA 2		FT ~~30~~ 36.08		EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: I2k024frm.dgn (I2k042) **PLOT DATE:** 06-AUG-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
BENNINGTON 3 TRAFFIC SIGN SUMMARY SHT 2 **SHEET** 64 **OF** 90