STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

PARK ST.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.094, RT.	A	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE SIGN AND POST LOCATED 21 FT NORTH OF POLE #19.			
NB	MM 0.101, RT.	A	S1-1	36	36	FYG		9.00								1.00		15								INSTALL NEW SIGN AND POST 58 FT NORTH OF POLE #19.	X		
		A	W16-9P	24	12	FYG	AHEAD	2.00																		INSTALL NEW SIGN BELOW THE SCHOOL SIGN.	X		
NB	MM 0.109, RT.	A	VR-345	12	18		NO PARKING HERE TO CORNER						X		X											REMOVE SIGN AND POST LOCATED 21 FT SOUTH OF POLE # 20.			
NB	MM 0.120, RT.	A	R3-9cP	30	12		BEGIN	2.50								1.00		15								INSTALL NEW SIGN AND POST 37 FT NORTH OF POLE # 20.	X		
		A	R8-3	24	24			4.00																		INSTALL SIGN BELOW THE NEW BEGIN SIGN LOCATED 37 FT NORTH OF POLE # 20.	X		
NB	MM 0.123, RT.	A	W11-2	30	30								X		X											REMOVE SIGN AND POST LOCATED 53 FT NORTH OF POLE # 20.			
		A	W16-7P	24	12								X													REMOVE SIGN BELOW THE PED SIGN LOCATED 53 FT NORTH OF POLE # 20.			
SB	MM 0.124, LT.	F	S4-3P	24	8	FYG	SCHOOL	1.33						I		1.00		15		AS PER FINAL INSPECTION SIGNS MOVED ON 7/8/13						INSTALL NEW SIGN AND POST 58 FT NORTH OF AND ACROSS FROM POLE # 20.	X		
		F	R2-1	24	30		SPEED LIMIT 25	5.00						I												INSTALL NEW SIGN BELOW THE SCHOOL PLAQUE 58 FT NORTH OF AND ACROSS FROM POLE # 20.	X		
										EA	EA	EA	EA 4	EA	EA 3		FT	FT 45	FT		LB	LB	LB	LB					
								SF 23.83	SF	EA 4				EA 3		EA 3	FT ~~45~~ 49.50			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA

BENNINGTON 3 TRAFFIC SIGN SUMMARY SHT 3 **SHEET** 65 **OF** 90