STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

PARK ST.
BENNINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		A	S5-2	24	30		END SCHOOL ZONE	5.00																		INSTALL NEW SIGN BELOW THE SPEED LIMIT SIGN LOCATED 137 FT SOUTH OF POLE #28.	X		
NB	MM 0.315, LT.	F	TOWN SIGN	12	18		NO PARKING						~~X~~ 2		X											REMOVE SIGN AND POST LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.			
SB	MM 0.315, LT.	F	S4-3P	24	8	FYG	SCHOOL	1.33								1.00		15								INSTALL NEW SIGN AND POST 52 FT NORTH OF AND ACROSS FROM POLE # 27.	X		
		F	R2-1	24	30		SPEED LIMIT 25	5.00																		INSTALL NEW SIGN BELOW THE SCHOOL SIGN LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.	X		
		F	S4-1P	24	10		6:00 AM TO 4:30 PM	1.67																		INSTALL NEW SIGN BELOW THE 25 MPH SPEED LIMIT SIGN LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.		53	
		F	S4-6P	24	10		MON-FRI	1.67																		INSTALL NEW SIGN BELOW THE 6:00 AM TO 4:30 PM SIGN LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.	X		
SB	MM 0.315, LT.	F	R3-9cP	30	12		BEGIN	2.50								1.00		15								INSTALL NEW SIGN AND POST TO THE RIGHT OF THE SCHOOL SIGN ASSEMBLY LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.	X		
		F	R8-3	24	24		R	4.00																		INSTALL NEW SIGN BELOW THE BEGIN SIGN LOCATED 52 FT NORTH OF AND ACROSS FROM POLE # 27.	X		
SB	MM 0.402, LT.	F	S4-3P	24	8		SCHOOL						X		X											REMOVE SIGN AND POST LOCATED 337 FT NORTH OF AND ACROSS FROM POLE #28.			
		F	R2-1	24	30		SPEED LIMIT 25 / R						~~X~~ 2													REMOVE SIGN BELOW THE SCHOOL SIGN LOCATED 337 FT NORTH OF AND ACROSS FROM POLE #28.			
										EA	EA	EA	EA ~~3~~ 5	EA	EA 2		FT	FT 30	FT		LB	LB	LB	LB					
								SF 21.17	SF	EA ~~3~~ 5				EA 2		EA 2	FT ~~30~~ 27.17			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA

BENNINGTON 3 TRAFFIC SIGN SUMMARY SHT 8 **SHEET** 70 **OF** 90