STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

DANBY BROOK ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 4.760, RT.	A	W1-10R	36	36			9.00								2.00		30								INSTALL NEW SIGN AND POSTS 118 FT NORTH OF A FIELD DRIVE.	X		
		A	W16-8P	36	8			2.00																		INSTALL NEW SIGN BELOW W1-10 R SIGN ON THE SAME POSTS.		53	
NB	MM 4.655, RT.	A	W1-5R	30	30			6.25								2.00		30								INSTALL NEW SIGN ON 2-POSTS 612 FT NORTH FROM A FIELD DRIVE.	X		
		A	W13-1P	18	18			2.25																		INSTALL NEW SIGN BELOW W1-5R SIGN ON THE INSIDE POST.	X		
		A	W7-3aP	24	18			3.00																		INSTALL NEW PLAQUE BELOW W1-5 R SIGN ON OUTSIDE POST.	X		
							KEELER ROAD																						
EB	MM 0.000, RT.	A	R1-1	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST AT THE NORTHEAST CORNER OF BROOK ROAD AND KEELER RD.	X		
		EF	D3-1	36	12			3.00																		INSTALL NEW SIGN ABOVE THE STOP SIGN PERPENDICULAR TO THE BROOK ROAD		53	
WB	MM 0.046, LT.	F	R2-1	24	30			5.00					X			1.00		15								REPLACE EXISTING SIGN 245 FT FROM KEELER RD AND BROOK RD INTERSECTION; THE SIGN IS ATTACHED TO A TREE. INSTALL ON NEW POST ABOUT 5 FT IN FRONT OF TREE.	X		
EB	MM 0.047, RT.	A	W3-1	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 250 FT NORTHEAST OF KEELER RD AND BROOK RD INTERSECTION.	X		
EB	MM 0.050, LT.	B	W1-6	48	24			8.00					0 X		X	2.00		30								REPLACE SIGN AND POST 265 FT NORTHEAST OF KEELER RD AND BROOK RD INTERSECTION.	X		
EB	MM 0.057, RT.	A	W1-6	48	24			8.00					0 X		X	2.00		30								REPLACE SIGN AND POST 300 FT NORTHEAST OF KEELER RD AND BROOK RD INTERSECTION.	X		
										EA	EA	EA	EA 42	EA	EA 3			FT 165	FT		LB	LB	LB	LB					
								SF 59.00	SF	EA 42				EA 3		EA 11		FT 165		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: I2k024frm.dgn (I2k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
DERBY TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 74 OF 90