STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

RIVER RD.
NEW HAVEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.000, RT.	A	R2-1	24	30		SPEED LIMIT 40	5.00								1.00		15								INSTALL NEW SIGN AND POST 400 FT WEST OF POLE # 20 / 20.	X		
EB	MM 0.015, RT. TO MM 0.261, RT.	A B		6	8		(26) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (26) BACK-TO-BACK 65 FT APART ON 13 POSTS. INSTALL FIRST POST ACROSS FROM POLE # 21 / 21.		4	
EB	MM 0.197, RT.	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN LOCATED 46 FT EAST AND ACROSS POLE # 23 / 23.			
		A	W1-5L	30	30								X													REMOVE ~~INSTALL NEW SIGN AND POST 121 FT EAST AND ACROSS POLE # 24 / 24.~~			
EB	MM 0.221, RT.	A	W1-4L	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 121 FT EAST AND ACROSS POLE # 24 / 24.	X		
EB	MM 0.246, RT.	A	W5-2	36	36		NARROW BRIDGE	9.00								2.00		30								INSTALL NEW SIGN ON 2 POSTS 15 FT WEST AND ACROSS POLE # 24 / 24.	X		
WB	MM 0.254, LT.	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		15								REPLACE SIGN AND POST AT SAME LOCATION, 58 FT EAST OF POLE # 24 / 24.	X		
EB	MM 0.272 +100, RT.	C	R2-1	24	30		SPEED LIMIT 35	5.00								1.00		15								INSTALL NEW SIGN AND POST 100 FT FROM THE EDGE OF RIVER RD ON HALPIN RD.	X		
								SF 30.25	SF	EA			EA ~~34~~	EA 2		EA 6		FT ~~90~~ 81.08		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: I2k024frm.dgn (I2k042) PLOT DATE: 06-AUG-2012
PROJECT LEADER: JLS DRAWN BY: TDS
DESIGNED BY: NLA CHECKED BY: NLA
NEW HAVEN TRAFFIC SIGN SUMMARY SHEET 1 SHEET 76 OF 90