STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

RIVER RD.
NEW HAVEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.272, RT.	D	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT HALPIN RD AND RIVER ROAD INTERSECTION	X		
		C	D3-1	36	12		River Rd	3.00					X													REPLACE SIGN ABOVE R1-1 AT SAME LOCATION. NORTHEAST CORNER OF THE INTERSECTION OF HALPIN RD & RIVER RD		53	
		A	D3-1	36	12		Halpin Rd	3.00					X													INSTALL NEW SIGN ABOVE THE HALPIN STREET NAME SIGN, PERPENDICULAR TO HALPIN RD ON SAME POST		53	
		C	R2-1	24	30		SPEED LIMIT 35						0 ~~X~~													REMOVE THE EXISTING 35 MPH SPEED LIMIT SIGN ON THE BACK OF THE STOP SIGN.			
EB	MM 0.277, RT.	A B		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST. INSTALL BEHIND THE GUARDRAIL AT THE BEGINNING OF THE TERMINAL (INSTALL ON THE EAST SIDE OF HALPIN RD).		5	
WB	MM 0.279, LT.	E	OM-3L	12	36			3.00					X		X	1.00		15								REPLACE SIGN AND POST ON THE LEFT SIDE OF RIVER ROAD AT SAME LOCATION, 42 FT FROM THE CENTER OF HALPIN RD.	X		
EB	MM 0.279, RT.	A	OM-3R	12	36			3.00					X		X	1.00		15								REPLACE SIGN AND POST ON THE RIGHT SIDE OF RIVER ROAD AT SAME LOCATION, 42 FT FROM THE CENTER OF HALPIN RD.	X		
WB	MM 0.321, LT.	F	OM-3R	12	36			3.00					X		X	1.00		15								REPLACE SIGN AND POST ON THE LEFT SIDE OF RIVER ROAD AT SAME LOCATION, 5 FT WEST AND ACROSS POLE # 26.	X		
EB	MM 0.321, RT.	B	OM-3L	12	36			3.00					X		X	1.00		15								REPLACE SIGN AND POST ON THE RIGHT SIDE OF RIVER ROAD AT SAME LOCATION, IN FRONT OF POLE # 26.	X		
								SF 24.25	SF	EA	EA	EA	EA ~~8~~ 7	EA	EA 5	EA 5	FT	FT 75 ~~75~~ 57.0	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: I2k024frm.dgn (I2k042) PLOT DATE: 06-AUG-2012
PROJECT LEADER: JLS DRAWN BY: TDS
DESIGNED BY: NLA CHECKED BY: NLA
NEW HAVEN TRAFFIC SIGN SUMMARY SHEET 2 SHEET 77 OF 90