STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

LINCOLN AVE.
RUTLAND CITY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.000, LT.	F	R1-2	36	36		YIELD	3.89					X		X	1.00		15								REPLACE SIGN AND POST AT WEST ST ON WEST SIDE OF LINCOLN AVE AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
SB	MM 0.000, LT.	GH	D3-1	42	12		Lincoln Ave	3.50					~~X~~ 0			1.00		15								REPLACE STREET NAME SIGN INSTALL ABOVE R1-2 SIGN ON SAME POST SIGN AT THE WEST SIDE OF LINCOLN AVE & WEST ST INTERSECTION.		53	
		EF	D3-1	30	12		West St	2.50					~~X~~ 0													INSTALL NEW SIGN ABOVE THE LINCOLN AVE STREET NAME SIGN AT THE WEST ST INTERSECTION WITH A 12" SIGN BRACKET		53	
NB	MM 0.096, RT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT GRANT AVE ON THE SOUTHEAST SIDE OF LINCOLN AVE AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
		A	W4-4P	24	12		CROSS TRAFFIC DOES NOT STOP	2.00																		INSTALL NEW SIGN BELOW THE NEW STOP SIGN ON THE SOUTHEAST SIDE OF LINCOLN AVE AT GRANT AVE.	X		
SB	MM 0.104, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT GRANT AVE ON THE NORTHWEST SIDE OF LINCOLN AVE AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
		F	W4-4P	24	12		CROSS TRAFFIC DOES NOT STOP	2.00																		INSTALL NEW SIGN BELOW THE NEW STOP SIGN ON THE NORTHWEST SIDE OF LINCOLN AVE AT GRANT AVE.	X		
NB	MM 0.206, RT.	C	W14-1	30	30		DEAD END	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT THE SOUTHEAST CORNER OF WILLIAMS ST AND LINCOLN AVE INTERSECTION	X		
SB	MM 0.206, LT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT WILLIAMS ST ON THE SOUTHWEST SIDE OF LINCOLN AVE AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
		H	W4-4P	24	12		CROSS TRAFFIC DOES NOT STOP	2.00																		INSTALL NEW SIGN BELOW THE NEW STOP SIGN ON THE SOUTHWEST SIDE OF LINCOLN AVE AT WILLIAMS ST.	X		
NB	MM 0.214, RT.	C	W14-1	30	30		DEAD END						X													REMOVE SIGN AT THE BACK OF THE STOP SIGN AT WILLIAMS ST ON THE NORTHEAST SIDE OF LINCOLN AVE.			
		D	R1-1	30	30		STOP	6.25					X		X	1.00		15								REMOVE SIGN AND POST AT WILLIAMS ST ON THE NORTHEAST SIDE OF LINCOLN AVE AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
		D	W4-4P	24	12		CROSS TRAFFIC DOES NOT STOP	2.00																		INSTALL NEW SIGN BELOW THE NEW STOP SIGN ON THE NORTHEAST SIDE OF LINCOLN AVE AT WILLIAMS ST.	X		
										EA	EA	EA	EA ~~87~~	EA	EA 5		FT	FT 105	FT		LB	LB	LB	LB					
								SF 49.14	SF	EA ~~87~~				EA 5		EA 7	FT ~~105~~ 95.91			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: NLA
RUTLAND CITY TRAFFIC SIGN SUMMARY SHT 1

PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 81 **OF** 90