STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

**LINCOLN AVE.
RUTLAND CITY**

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.704, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT NORTH ST ON THE NORTHWEST SIDE OF LINCOLN AVE.	X		
		F	R1-3P	18	6		ALL WAY	0.75					X													REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE NORTHWEST SIDE OF LINCOLN AVE AT NORTH ST.	X		
NB	MM 0.950, RT.	A	W3-1	30	30			6.25					X		X	1.00		15								REPLACE SIGN AND POST ABOUT 500 FT SOUTH OF VERNON ST AND INSTALL NEW SIGN AND POST AT SAME LOCATION.	X		
NB	MM 1.046, RT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT VERNON ST ON THE SOUTHEAST SIDE OF LINCOLN AVE .	X		
		A	R1-3P	18	6		ALL WAY	0.75					X													REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE SOUTHEAST SIDE OF LINCOLN AVE AT VERNON ST.	X		
SB	MM 1.046, LT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT VERNON ST ON THE SOUTHWEST SIDE OF LINCOLN AVE.	X		
		H	R1-3P	18	6		ALL WAY	0.75					X													REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE SOUTHWEST SIDE OF LINCOLN AVE AT VERNON ST.	X		
NB	MM 1.054, RT.	D	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT VERNON ST ON THE NORTHEAST SIDE OF LINCOLN AVE.	X		
		D	R1-3P	18	6		ALL WAY	0.75					X													REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE NORTHEAST SIDE OF LINCOLN AVE AT VERNON ST.	X		
SB	MM 1.054, LT.	F	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT VERNON ST ON THE NORTHWEST SIDE OF LINCOLN AVE .	X		
		F	R1-3P	18	6		ALL WAY	0.75					X													REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE NORTHWEST SIDE OF LINCOLN AVE AT VERNON ST.	X		
NB	MM 1.276, RT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE SIGN AND POST AT FIELD AVE ON THE SOUTHEAST SIDE OF LINCOLN AVE.	X		
		A	R1-3P	18	6		ALL WAY	0.75					X													PLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE SOUTHEAST SIDE OF LINCOLN AVE AT FIELD AVE.	X		
								SF ~~49.00~~ 48.25	SF	EA	EA	EA	EA ~~14~~ 13	EA	EA 7	EA 7		FT ~~105~~ 96.50		EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: I2k024frm.dgn (I2k042) **PLOT DATE:** 06-AUG-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
RUTLAND CITY TRAFFIC SIGN SUMMARY SHT 5 **SHEET** 85 **OF** 90