STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 6

**LINCOLN AVE.**
**RUTLAND CITY**

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK | SIGN DETAIL DETAIL IN SHSM | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SB | MM 1.276, LT. | H | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE SIGN AND POST AT FIELD AVE ON THE SOUTHWEST SIDE OF LINCOLN AVE. | X | | |
| | | H | R1-3P | 18 | 6 | | ALL WAY | 0.75 | | | | | X | | | | | | | | | | | | | REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE SOUTHWEST SIDE OF LINCOLN AVE AT FIELD AVE. | X | | |
| NB | MM 1.284, RT. | D | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE SIGN AND POST AT FIELD AVE ON THE NORTHEAST SIDE OF LINCOLN AVE. | X | | |
| | | D | R1-3P | 18 | 6 | | ALL WAY | 0.75 | | | | | X | | | | | | | | | | | | | REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE NORTHEAST SIDE OF LINCOLN AVE AT FIELD AVE. | X | | |
| SB | MM 1.284, LT. | F | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE SIGN AND POST AT FIELD AVE ON THE NORTHWEST SIDE OF LINCOLN AVE. | X | | |
| | | F | R1-3P | 18 | 6 | | ALL WAY | 0.75 | | | | | X | | | | | | | | | | | | | REPLACE EXISTING 4-WAY SIGN AND INSTALL BELOW THE NEW STOP SIGN ON THE NORTHWEST SIDE OF LINCOLN AVE AT FIELD AVE. | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | |