STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

TOWN TOTALS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							BENNINGTON - SOUTH ST. - SUBTOTAL	90.50					10		8	14		210											
							BENNINGTON - MATTESON RD. - SUBTOTAL	163.32					25		23	27		405											
							BENNINGTON - PARK ST. - SUBTOTAL	194.17		2			29	2	19	27		405											
							DANBY - BROOK RD. - SUBTOTAL	120.25					6		4	23		345											
							NEW HAVEN - RIVER RD. - SUBTOTAL	94.25					15		10	16		240											
							RUTLAND - LINCOLN AVE. - SUBTOTAL	263.42					62		36	38		570											
								SF 925.91	SF	EA 149				EA 102		EA 145	FT 2175			EA	LB								
										EA 2	EA	EA	EA 147	EA 2	EA 100		FT	FT 2175	FT		LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: HES HSIP(6)

FILE NAME: 12k024frm.dgn (12k042)
PROJECT LEADER: JLS
DESIGNED BY: N/A
TOWN TOTALS TRAFFIC SIGN SUMMARY SHEET
PLOT DATE: 06-AUG-2012
DRAWN BY: TDS
CHECKED BY: N/A
SHEET 88 **OF** 90