

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	BRIDGE NO. D11	BRIDGE NO. 2	BRIDGE NO. D18	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							119	134	238		491		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							13	11	13		37		CWT	EMULSIFIED ASPHALT	404.65				
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
							28	25	34		87		GAL	WATER REPELLENT, SILANE	514.10				
							1210	871	1101		3182		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								64	66		130		LF	JOINT SEALER, HOT POURED	524.11				
									176		176		LF	JOINT SEALER, POLYURETHANE	524.21				
							1210	1004	1101		3315		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
							61	44	56		161		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
							182	131	166		479		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
							15	25	12		52		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
							10886	7834	9901		28621		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
							10	10	10		30		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
							33	21			54		GAL	REPOINTING GRANITE BRIDGE CURB	616.225				
							3	2	2		7		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
							188	194	188		570		LF	TEMPORARY TRAFFIC BARRIER	621.90				
							188	194	188		570		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
							91	66	83		240		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							150	150	150		450		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL (CSH OVER US 4 - BRIDGE NO. 2)	641.10				
									1		1		LS	TRAFFIC CONTROL (TH 22 OVER US 4 - BRIDGE NO. D18)	641.10				
							1				1		LS	TRAFFIC CONTROL (TH 5 OVER US 4 - BRIDGE NO. D11)	641.10				
							2	2	2		6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								683			683		LF	4 INCH WHITE LINE	646.20				
							897	683			1580		LF	4 INCH YELLOW LINE	646.21				
								1700			1700		LF	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6011				
							48	48	48		144		LF	TEMPORARY 24 INCH STOP BAR, TEMPORARY PAVEMENT MARKING TAPE	646.6811				
								85			85		EACH	RAISED PAVEMENT MARKERS, TYPE II	646.75				
							300	600			900		SF	PAVEMENT MARKING MASK	646.86				
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
							1	1	1		3		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620				
							1	1	1		3		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
							1	1	1		3		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
							224	199	232		655		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				