



SAWED PAVEMENT JOINT DETAIL

(NOT TO SCALE)

* JOINT IS TO BE LOCATED ACCURATELY BY STRING LINING, OR OTHER MEANS, PRIOR TO PAVING, SO THAT THE SAW CUTS WILL BE MADE DIRECTLY OVER THE END OF CONCRETE DECK. JOINT SHALL BE CUT DRY IN A SINGLE PASS AND BE SEALED WITHIN 24 HOURS OR PRIOR TO EXPOSURE TO TRAFFIC. JOINT SHALL BE CLEANED PRIOR TO APPLYING THE JOINT SEALER. ALL WORK SHALL BE PAID UNDER ITEM 524.11, "JOINT SEALER, HOT Poured".

CLD 13-0203 MODEL: Jnts01

PROJECT NAME: CASTLETON-RUTLAND	FILE NAME: z13b116-jnts.dgn	PLOT DATE: 3/21/2014
PROJECT NUMBER: BF MEMB(37)	PROJECT LEADER: JPB	DRAWN BY: MWS
	DESIGNED BY: NDC	CHECKED BY: JPB
	PAVEMENT JOINT DETAILS	SHEET 9 OF 28



540 Commercial Street, Manchester, NH 03101
 (603) 668-8223 • Fax: (603) 668-8802
 cld@cldeengineers.com • www.cldeengineers.com
 Maine • New Hampshire • Vermont