

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	RAILROAD	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							700				700		CY	COMMON EXCAVATION	203.15	12			
							180				180		CY	SAND BORROW	203.31				
							35				35		CY	GRANULAR BORROW	203.32	2			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							500				500		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	19			
							75				75		TON	AGGREGATE SHOULDERS	402.12	3			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
							80				80		LF	6 INCH UNDERDRAIN PIPE	605.10	2			
							2				2		MGAL	DUST CONTROL WITH WATER	609.10				
							320				320		CY	STONE FILL, TYPE II	613.11				
							200				200		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	8			
							175				175		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	3			
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							1200				1200		LF	DURABLE 4 INCH YELLOW LINE	646.410				
									2		2		EACH	DURABLE RAILROAD CROSSING SYMBOL	646.510				
									80		80		SY	GEOTEXTILE UNDER RAILROAD BALLAST	649.21	3			
							240				240		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							15				15		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	3			
								150			150		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	5			
							5				5		LB	SEED	651.15	1			
							35				35		LB	FERTILIZER	651.18	4			
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							35				35		CY	TOPSOIL	651.35	1			
							1				1		LS	EPSC PLAN	652.10				
							50				50		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							10				10		CY	VEHICLE TRACKING PAD	653.35				
							33				33		SF	TRAFFIC SIGNS, TYPE A	675.20				
							30				30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							6				6		EACH	REMOVING SIGNS	675.50				
									22000		22000		DL	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.615				
									1		1		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				

PROJECT NAME:	NEW HAVEN	PLOT DATE:	02/17/2017
PROJECT NUMBER:	STP 2035 (19)	DRAWN BY:	W. TSE
FILE NAME:	z13g606qty.xls	CHECKED BY:	R. O'BLENIS
PROJECT LEADER:	R. O'BLENIS	DESIGNED BY:	W. TSE
QUANTITY SHEET #1		SHEET	8 OF 42