


**ERITECH<sup>®</sup>**

- Features a single-use ceramic mold which eliminates the need for a mold and frame and / or handle clamps.
- Produces a permanent connection that will not loosen or corrode.
- Fits copper-bonded (threaded and plain), galvanized and stainless steel ground rods.
- Simple to use.
- NEC<sup>®</sup> compliant
- cULus<sup>®</sup> Listed
- Rural Utilities Service (RUS) accepted

## **CADWELD<sup>®</sup> ONE SHOT**

For Connections to Ground Rods



The CADWELD<sup>®</sup> ONE SHOT produces a permanent exothermically welded connection to a ground rod that will not loosen, corrode away, or increase in resistance for the life of the installation.



Position CADWELD ONE SHOT and wire on prepared ground rod. Dump the welding material into the ceramic crucible.



Set the lid on the CADWELD ONE SHOT body and add the starting material.



Initiate the reaction with T320 flint ignitor



The reaction produces a finished permanent exothermic connection



**ERICO<sup>®</sup>**